



Interior Finishes Specifications



Project No.: 11-302

Prepared By:
Hefele Makowka Design Associates Inc.
146 Laird Drive
Suite 301
Toronto, Ontario
M4G 3V7

Contact: Margit Hefele tel: (416) 944-0802 fax: (416) 944-0836

e-mail: info@hminteriordesign.com

Re-Issued for Carpet Tender with added Winter Carpet – March 26, 2014
Re-Issued for Interior Finishes Tender – March 13, 2014
Issued for Interior Finishes Tender – November 14, 2013

General Note:

All area denotations noted in this Finishes Specification Manual must be verified and confirmed with the Room/Door Finishes Schedules, Finishes Plans, Elevations and Details. Any discrepancies are to be brought to the designer's attention prior to costing, ordering of any product.



Specifications Page No.: 2

Project: Argento Condo Project No. 11-302

Index

Section	<u>Item</u>	Page No.
	Index	2
1.0	General Instructions and Legend 1.1 General Notes to Suppliers & Installers 1.2 Legend of Finishes Symbols	3-4 5
2.0	 Wall, Ceiling and Floor Finishes 2.1 - General Notes - Wall and Ceiling 2.2 - General Notes - Floor Finishes 2.3 - Carpets 2.4 - Porcelain & Ceramic Tiles 2.5 - Wood & Cork Flooring 2.6 - Stone Finishes: Slab & Tile 2.7 - Vinyl Tile & Vinyl Base 2.8 - T-Bar, Acoustic Ceiling Tiles & Stretched Ceilings 2.9 - Wallcoverings 2.10 - Paints 	6 7-8 9-11 12-19 20-21 22-23 24 25-26 27-30 31-37
3.0	Metals 3.1 - General Notes 3.2 - Finishes	38 38
4.0	Plastic Laminates 4.1 - General Notes 4.2 - Finishes	39 39-41
5.0	Woods and Veneers 5.1 - General Notes 5.2 - Finishes	42 42-43
6.0	Millwork 6.1 - General Notes	44-45



Specifications Page No.: 3

Project: Argento Condo Project No. 11-302

Section 1.0

General Instructions and Legend

1.1 General Notes to Suppliers & Installers

- 1. Contractor must verify all dimensions and site conditions, and advise Designer of any discrepancies. Drawings not to be scaled.
- 2. Finishes Specification Manual is to be used in conjunction with all Working Drawings and Details.
- 3. All work shall conform to all applicable governing Codes and building requirements. Contractor to advise Designer immediately of any contravention of Building Codes prior to proceeding with work.
- 4. <u>All</u> wood solids and veneers to be fire-rated as necessary to meet all Building Code and Fire Code Regulations.
- 5. Provide adequate blocking and reinforcing in walls where millwork, fixtures and equipment are to be installed.
- 6. General Contractor to provide shop drawings for all millwork, counters, built-ins, manufactured items, etc. for review and approval by Hefele Makowka Design Associates Inc.
- 7. Verify all dimensions on site prior to production of Shop Drawings and prior to proceeding with work.
- 8. The Designer is to approve all finishes and materials prior to installation.



Specifications Page No.: 4

Project: Argento Condo Project No. 11-302

Section 1.0

General Instructions and Legend

1.1 General Notes to Suppliers & Installers

9. <u>Samples</u>

- a) The Contractor shall submit samples to the Designers as required in each section of the specifications in sufficient time to permit review and approval.
- b) All samples shall be delivered to the Designers or to the site at the request of the Designers.
- c) The approved samples shall be retained and used for control samples and the Contractor shall remove the rejected samples.
- d) Where samples are rejected, new samples shall be submitted as soon as possible after notification of rejection.
- e) The cost of all samples shall be borne by the Contractor.

General Note:

The Designer shall not warrant or be responsible for the quality of materials / articles, specified for / or installed in the Client's premises: or for structural conditions of said premises; or for acts, work, or services of any employee or contractor of the Client.

General Note:

All area denotations noted in this Finishes Specification Manual must be verified and confirmed with the Room/Door Finishes Schedules, Finishes Plans, Elevations and Details. Any discrepancies are to be brought to the designer's attention prior to costing and/or ordering of any product.



Specifications Page No.: 5

Project: Argento Condo Project No. 11-302

Section 1.0

General Instructions and Legend

1.2 Legend of Finishes Symbols

- **ACT- Denotes Acoustical Tile & Stretched Ceiling**
- **C-** Denotes Carpet
- **CT-** Denotes Ceramic Tile
- **GS-** Denotes Granite Slab
- **GT-** Denotes Granite Tile
- **HW-** Denotes Hardwood Floor
- **M-** Denotes Metal
- **MR-** Denotes Mirror
- **MS-** Denotes Marble Slab
- **MT-** Denotes Marble Tile
- P- Denotes Paint Finish
- PL- Denotes Plastic Laminate
- S- Denotes Wood Type & Stain Finish
- **SC-** Denotes Solid Surface
- **VB-** Denotes Vinyl Base
- **VT-** Denotes Vinyl Tile
- W- Denotes Wallcovering
- WA- Denotes Washroom Accessory



Specifications Page No.: 6

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.1 <u>General Notes – Wall and Ceiling Finishes</u>

- 1. Refer to Room Finishes Schedules, Reflected Ceiling Plans, Elevations, Details and Millwork Drawings.
- 2. Contractor to verify all site conditions and dimensions prior to ordering and installation.
- 3. All surfaces must be smooth, dry, and free from dust and grease and carefully prepared for any good quality wallcovering.
- 4. Application of prime coats and finish coats shall follow faithfully the highest industry standards and procedures.
- 5. All gypsum board shall receive one coat of sealer primer and two coats of finish paint.
- 6. Co-ordinate with the Designers for each colour and finish, a test location onsite for the approval of the paint colours. The Designers may request reasonable adjustments to the paint colour even though the applied test area matches the drawn down sample.
- 7. Absorbent walls should be sized.
- 8. All wallcoverings should be of one dye lot per colour.
 Full lengths must be used.
 Check to ensure proper pattern and colour prior to installation.
 Return wallcovering into reveals and around columns as required.
 All wallcoverings must comply with the local fire codes.
 Avoid getting adhesive on the face of the material.



Specifications Page No.: 7

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.2 General Notes – Floor Finishes

- 1. Refer to Floor Finishes Drawings, Room Finishes Schedules, Reflected Ceiling Plans and Details.
- 2. Provide all labour, materials, products, equipment and services required and/or indicated on the drawings and specified herein for the installation of floor finishes.
- 3. Installer to verify all site conditions and dimensions prior to ordering and installation.
- 4. Carpet layout from installer is required prior to commencing work.

 Carpet insets and borders must be cut very carefully and use a high quality seam sealer to ensure long lasting joints and prevents loosening of pile.

 Carpet base to have pre-finished colour-matched surged edges.
- 5. Carpet to continue under shelves and recessed base of furniture and/or millwork.
- 6. Install all carpet to center of door unless otherwise noted.
- 7. All carpet lengths to be installed with nap running in one direction.
- 8. Vinyl tile to be installed directly to the concrete finish using manufacturer's recommended adhesive; wax and polish prior to tenants' occupancy.
- 9. All areas with vinyl tile flooring to receive 4" vinyl base as specified.
- 10. Ceramic floor tiles shall be set in thin portland cement mortar setting bed, 10mm nominal or as required.
- 11. Make cut edges smooth, even and free from chipping. Edges resulting from chipping are not acceptable.



Specifications Page No.: 8

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.2 <u>General Notes – Floor Finishes Con't</u>

- 12. Ceramic tile to continue under recessed base of counters and under shelves where applicable.
- 12. Align grout lines in floor and tile base where applicable. Make joints between tiles uniform, plumb and straight with adjacent units flush and level.
- 13. All exposed edges on ceramic tiles to be finished to match colour of tile.
- 14. Dye lots of all ceramic / porcelain trims must be identical to relevant field tiles.
- 15. Contractor / installer to prepare floor accordingly to receive granite and/or marble tiles.
- 16. All exposed granite and/or marble tile edges to be polished.
- 17. Provide granite or marble slab thresholds as specified on floor finishes plans unless otherwise noted.
- 18. Installers to provide suitable edge protection and/or transition strips in all locations if required where two different flooring materials meet.

 Ensure that all transition of flooring materials and strips are <u>installed flush</u> and are barrier free compliant.

All required hardware to be by <u>Schluter Systems</u>, finish: Stainless Steel. Contractor to provide samples of all proposed metal transition strips and/or floor and wall metal inlays to designer for approval.



Specifications Page No.: 9

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.3 <u>Carpets</u>

General Note:

Installers to provide suitable edge protection and/or transition strips in all locations if required where two different flooring materials meet. Ensure that all transition of flooring materials and strips are installed flush and are barrier free compliant.

All required hardware to be by <u>Schluter Systems</u>, finish: Stainless Steel.

Contractor to provide samples of all proposed metal transition strips and/or floor and wall metal inlays to designer for approval.

C-1 Supplier: The C/S Group

Contact: Cindy Noah (905) 273-2611

Series: Pedimat - Flush Recessed (Into surrounding floor tiles)

Rail & Frame Finish: Clear Anodized (C)

Carpet Tread: 7323 Castle Gray

Area No.: P-01, P2-01, P1-01, Vestibules,

P-03, P2-03, P1-03 North Air Locks,

P2-04, P1-04, P-04 South Air Locks, G-01 Vestibule

C-2 Supplier: Mohawk Group

Contact: Rhonda Russel (416) 460-9375

Type: Broadloom

Width: 12'-0

Series: Karastan Contract Pattern/No.: Insatiable KC152 Colour/ No.: Allurement / # 695

Repeat: 1 ½" W

Content: Ultron Nylon, Type 6.6

Indoor Air Quality: IAQ Green Label Plus # 3802

Weight: 28 oz

W/Base: 4" High MS-1

Area No.: G-02 Main Lobby/Lounge, G-04 Concierge - Inset



Specifications Page No.: 10

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.3 Carpet Con't

C-3 Supplier: Bentley Prince Street

Contact: Jo Anne Crompton (647) 435-1074

Type: Broadloom Width: 12'-6"

Series: International Glamour

Pattern/No.: 81G340630R

Colour/ No.: Super Viva / # 880114

Repeat: Random

Content: Antron Brilliance CF Nylon

Indoor Air Quality: IAQ Green Label Plus #4435

Weight: 34oz

W/Base: 6" High Wood Base, S-1

Area No.: G-25 Party Room – Inset

C-4 Supplier: The McKar Group

Contact: Ian DeSouza (905) 567-1505

Manufacturer: Milliken Hospitality

Type: Carpet Tile

Size: 36" x 36" Modular

Series: Tetrapoint, DR/Mat. ID 00401912

Pattern/No.: T135NK9LTE-A13001

Colour Way.: 1UMA
Repeat: 36" x 36"
Installation: Monolithic

Content: 100% WearOn Continuous Filament Nylon, Type 6,6

Indoor Air Quality: Green Label Plus Certified #2860

Weight: 20 oz.

W/Base: 5 1/2" High Wood Base Painted P-11

Area No.: T-01 Elevator Lobby, T-02 Suite Corridor - Broadloom



Specifications Page No.: 11

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.3 Carpet Con't

C-5 Supplier: Lexmark Carpet Mills

Contact: Andre Barci (905) 669-5533

Type: Broadloom

Width: 12'-0"

Series:: Lexshield Plus Pattern/No.: Zuma / #615

Colour/ No.: #378

Repeat: 18"W x 31.75"L

Content: Solution Dyed Nylon with Action Bac

Indoor Air Quality: CRI Green Label Plus

Weight: 32oz

W/Base: 6" High P-16

Area No.: G-15 Theatre

C-6 Supplier: VI Floor Canada Ltd.

Contact: Scott Pope (416) 521-9014 x220

Type: Broadloom Width: 12'-0"
Series: Patcraft

Pattern/No.: Glamorous / # Z6471 Colour/ No.: Grandeur / # 00518

Repeat: 36"W x 36"L

Content: Eco Solution Q Nylon

Indoor Air Quality: CRI Green Label Plus

Weight: 34oz

W/Base: As per Builder's Standard

Area No.: G-06 Office Reception, G-07 Admin Office,

G-09 Boardroom, G-50 Guest Suite

2.3 Carpet Con't



Specifications Page No.: 12

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.3 Carpet Con't

C-7 Supplier: VI Floor Canada Ltd.

Contact: Jane Shackelton (416)-521-9014

Series: Super Nop Commercial Matting (Winter Carpet)

Colour: # 1115

Fabric Fibre: 100% ASOTA

Dye Method: Solution Dyed Polypropylene

Face Weight: 1750 gr/m² (52 ounces per square yard)

Backing: Eco-DI-back ® natural-synthetic composite rubber

Weight: 3200 gr/m² (94 ounces per square yard)

Width: 200 cm (6'-7") Length: 21 m (69") Total Thickness: 12.5mm (0.5")

Area No.: G-02 Main Lobby/ Lounge, G-11 Corridor,

G-51 Elevator lobby



Specifications Page No.: 13

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 **Ceramic Tile**

General Note:

Installers to provide suitable edge protection and/or transition strips in all locations if required where two different flooring materials meet. Ensure that all transition of flooring materials and strips are installed flush and are barrier free compliant.

All required hardware to be by Schluter Systems, finish: Stainless

Steel.

Contractor to provide samples of all proposed metal transition strips and/or floor and wall metal inlays to designer for approval.

Note:

- All ceramic tiles to be ordered and installed with all available trims, i.e. nosings, caps, cove bases, edges, etc., as required for a complete, neat and sealed installation.
- All tiles to be ordered well in advance of installation due to an approximate delivery time of 6-8 weeks.

CT-1 **Supplier:** Ciot

> **Contact:** Badr Rauhi Salhia (416) 739-8000

Series: Tecnica Eiger

Colour/No: Grigio 12" x 24" Size:

Grout: Mapei #02 Pewter W/Base: 4" High MS-1

Area No.: G-01 Vestibule, G-02 Lobby/Lounge,

G-05 Office Corridor

G-11 Corridor, G-15a Foyer,

G-17 Corridor, G-51 Elevator Lobby

W/Base: 4" High CT-1

Area No.: G-08 Servery, G-10 Storage, G-12 Mail Pick Up,

> G-19 Men's Washroom, G-21 Women's Washroom, G-28 Fitness Studio Corridor, G-29 Men's Vestibule,

G-33 Women's Vestibule

W/Base: N/A

Area No.: Elevator Cabs 1, 2, 3 - Floor



Specifications Page No.: 14

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 <u>Ceramic Tile Con't</u>

CT-2 Supplier: Saltillo Imports Inc.

Contact: Alisa Biunno (416) 441-2224 X222

Series: Metal

Pattern/No: Checker Board / #SM01

Colour/No: Stainless Steel

Size: 3/4" x 3/4"

Grout: Mapei #02 Pewter W/Base: 4" High MS-1

Area No.: G-02 Lobby/Lounge, G-05 Office Corridor,

G-11 Corridor, G-15a Foyer, G-17 Corridor,

G-51 Elevator Lobby - Floor Accent

W/Base: 4" High MS-1

Area No.: Elevator Cab 1, 2, 3 - Floor Accent

CT-3 Supplier: Olympia Tile

Contact: Robin Zandi (416) 785-9555 x316

Series: Spark

Colour/No: Carbon (Black) / # WA.SP.CBN.1224

Size: 12" x 24"

Grout: Mapei #47 Charcoal

W/Base: 6" High CT-3

Area No.: P-01, P2-01, P1-01 Vestibules,

P-02, P2-02, P1-02, Elevator Lobbies - Floor



Specifications Page No.: 15

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 Ceramic Tile Con't

CT-4 Supplier: Ceragres

Contact: Rob Dibiasi (416) 420-9930

Series: Caesar Change

Colour/No: Forge Size: 12"x24"

Grout: Mapei #47 Charcoal

W/Base: 4" High PL-6 / 4" High CT-4

Area No.: G-25a Bar / G-26 Party Room Servery - Floor

CT-5 Supplier: Deco-Tile

Contact: Denise West (416) 413-7985

Series: Wings

Colour/No: Sumi-E Hida Natural

Size: 1" x 1"

Grout: StarGlass #671 Hematite

(Andy Gamper 416-741-2256)

W/Base: N/A

Area No.: G-25a Bar – Bar Front & Back Wall

CT-6 Supplier: Savoia

Contact: Anthony Ondretti (416) 789-7778

Series: As per Builder's Standard

Colour/No: Teoroma Perla (Order #717236)

Size: 13" x 13"

Grout: Mapei #27 Silver W/Base: 4" High CT-6

Area No.: G-50 Guest Suite Washroom – Floor & Tub Surround



Specifications Page No.: 16

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 <u>Ceramic Tile Con't</u>

CT-7 Supplier: Olympia Tile

Contact: Robin Zandi (416) 785-9555 ext.316

Series: Rosedale

Colour/No: Charcoal / # OV.RR.CHA.1212

Size: 12" x 12"

Grout: Mapei #47 Charcoal

W/Base: 4" High CT-7

Area No.: G-03 CACF, G-40 Loading Area Airlock,

G-49 Moving Room - Floor

W/Base: N/A

Area No.: G-38 Refuse, T-03 Refuse - Floor & Wall (Full height)

G-14 Janitor Room – Floor & Wall (6'-0" A.F.F)

CT-8 Supplier: Stone Tile

Contact: Nancy Brenner (416) 515-9000 ext 232

Series: Laminam / Filo

Colour/No: Ghisa

Size: 300cm Length x 100cm Width x 3mm Thick

Grout: <u>1mm Grout Line</u>

Mapei #47 Charcoal

W/Base: N/A

Area No.: G-25a Bar – Millwork

Critical Note: Installer to ensure unglazed ceramic slab is installed on

cement board, concrete or gypsum board substrate as outlined in the manufacturers installation guidelines.

Refer to the Laminam Technical Manual for

installation instructions.



Specifications Page No.: 17

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 Ceramic Tile Con't

CT-9 Supplier: Dal Tile

Contact: Margaret Cimicata (905) 850-4390 Series: Keystones Unglazed Ceramic Mosaics

Colour/No.: Uptown Taupe Speckle / #D202 Size: 2" x 2" (sheet size 12" x 12") Grout: Mapei #11 Sahara Beige W/Base: 1" High Cove Base CT-10

Area No.: G-30 Men's Change Room, G-32 Men's Shower,

G-34 Women's Change Room, G-36 Women's Shower – Floor G-31 Men's Steam Room, G-35 Women's Steam Room

- Floor & Bench

CT-10 Supplier: Dal Tile

Contact: Margaret Cimicata (905) 850-4390 Series: Keystones Unglazed Ceramic Mosaics

Colour/No.: Uptown Taupe Speckle / #D202 Size: 2" x 1" High Cove Base #C833

Grout: Mapei #11 Sahara Beige

W/Base: N/A

Area No.: G-30 Men's Change Room, G-31 Men's Steam Room,

G-32 Men's Shower, G-34 Women's Change Room, G-35 Women's Steam Room, G-36 Women's Shower –

Cove Base



Specifications Page No.: 18

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 <u>Ceramic Tile Con't</u>

CT-11 Supplier: Dal Tile

Contact: Margaret Cimicata (905) 850-4390 Series: Keystones Unglazed Ceramic Mosaics

Colour/No.: Biscuit / #D317

Size: 2" x 2" (sheet size 12" x 12")

Grout: Mapei #12 Mist

W/Base: 1" High Cove Base CT-10

Area No.: G-31 Men's Steam Room,

G-35 Women's Steam Room – Floor & Ceiling

G-30 Men's Change Room

G-34 Women's Change Room – Floor, Ceiling (Shower)

& Locker Bench

CT-12 Supplier: Savoia

Contact: Anthony Ondretti (416) 789-7778

Series: Soul

Pattern: Charme (Order # 575234)

Colour/No.: Cacao / 575234

Size: 10" x 30" (stacked horizontally)

Grout: Mapei #12 Mist

W/Base: 1" High Cove Base CT-10

Area No.: G-30 Men's Change Room, G-31 Men's Steam Room,

G-32 Men's Shower, G-34 Women's Change Room, G-35 Women's Steam Room, G-36 Women's Shower –

Wall (Accent)



Specifications Page No.: 19

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 <u>Ceramic Tile Con't</u>

CT-13 Supplier: Savoia

Contact: Anthony Ondretti (416) 789-7778

Series: Soul

Pattern: Ivory Wood (Order # 595226)

Colour/No.: Ivory / # 575226

Size: 10" x 30" (stacked horizontally)

Grout: Mapei #12 Mist

W/Base: 1" High Cove Base CT-10

Area No.: G-30 Men's Change Room, G-31 Men's Steam Room,

G-32 Men's Shower, G-34 Women's Change Room, G-35 Women's Steam Room, G-36 Women's Shower -

G-35 Women's Steam Room, G-36 Women's Shower –

Wall (Main Field)

CT-14 Supplier: Dal Tile

Contact: Margaret Cimicata (905) 850-4390 Series: Keystones Unglazed Ceramic Mosaics

Colour/No.: Uptown Taupe Speckle / #D202

Size: Nosing # C701

Grout: Mapei #11 Sahara Beige

W/Base: N/A

Area No.: G-31 Men's Steam Room, G-35 Women's Steam Room

- Bench Nosing



Specifications Page No.: 20

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.4 <u>Ceramic Tile Con't</u>

CT-15 Supplier: Ceragres

Contact: Rob Dibiasi (416) 420-9930

Series: Mosaics

Pattern/No: Onix Fuseglass / AFUSBROMOS1

Colour/No.: Bronze / #FU040

Size: 1" x 1"

Grout: StarGlass #671 Hematite

(Andy Gamper 416-741-2256)

W/Base: 4" High CT-1

Area No.: G-19 Men's Washroom, G-21 Women's Washroom –

Wall (toilet/sink wall only)

CT-16 Supplier: Cercan Tile

Contact: Cristina Delago (416) 413-9008

Series: Mosaics

Colour/No.: Silver Sky & White Mix

Size: 15mm x 15mm on 12" x 12" sheet

Grout: TEC AccuColorEFX Epoxy Grout #934 DeLorean Gray

(Irene Chan 416-785-5165)

W/Base: N/A

Area No.: G-02 Lobby/Lounge – Water Feature Only



Specifications Page No.: 21

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.5 Wood & Cork Flooring

General Note:

Installers to provide suitable edge protection and/or transition strips in all locations if required where two different flooring materials meet. Ensure that all transition of flooring materials and strips are installed flush and are barrier free compliant.

All required hardware to be by **Schluter Systems**, finish: Stainless

Steel.

Contractor to provide samples of all proposed metal transition strips and/or floor and wall metal inlays to designer for approval.

HW-1 Supplier: Torlys

Contact: Laura Binni (416) 525-8333

Type: Laminate Series: Vogue

No.: QS-UVG1390 Colour: Rustic Oak Light

Plank Size: 3/8" x 6- 1/8" x 54 -11/32" c/w Underlay: Torlys Safe and Sound W/Base: 4 1/2" High Wood Base S-1

Area No.: G-25 Party Room, G-22 W.I.C

HW-2 Supplier: Torlys

Contact: Laura Binni (416) 525-8333

Type: Cork

Series: Florence Designer
No.: CCU92669-FSC-MX

Colour: Nunavut

Plank Size: 5/8" x 7-1/2" x 68 3/4"

W/Base: 4" High P-7

Area No.: G-23 Exercise Room, G-24 Yoga Studio, G-27 Fitness

Studio Foyer



Specifications Page No.:22

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.5 Wood & Cork Flooring Con't.

HW-3 Supplier: Torlys

Contact: Laura Binni (416) 525-8333

Type: Laminate Series: Vogue

No.: QS-UVG1393 Colour: Rustic Oak Grey

Plank Size: 3/8" x 6- 1/8" x 54 -11/32" c/w Underlay: Torlys Safe and Sound

W/Base: 6" High PL-1

Area No.: G-16 Dining Room



Specifications Page No.: 23

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.6 Stone Finishes: Marble Slab & Marble Tile

General Note:

Installers to provide suitable edge protection and/or transition strips in all locations if required where two different flooring materials meet. Ensure that all transition of flooring materials and strips are installed flush and are barrier free compliant.

All required hardware to be by <u>Schluter Systems</u>, finish: Stainless Steel.

Contractor to provide samples of all proposed metal transition strips and/or floor and wall metal inlays to designer for approval.

- Material samples of all specified stone slabs and tiles <u>of current stock</u> must be submitted to the Designer for approval prior to ordering/installation.
- <u>All stone slab & tiles to be ordered well in advance</u> of installation due to an approximate <u>delivery time of 6-8 weeks.</u>
- Contractor to provide shop drawings pertaining to all stone slab installation denoting seam layouts, joints, trim & edge details, etc. for designer's approval prior to installation.

MS-1 Supplier: Ciot

Contact: Aaron Huynh (416) 739 8000

Type: Marble Slab Colour/No.: Bianco Carrara

Finish: Polished Size: ³/₄" Thick

Area No.: G-02 Lobby/Lounge, G-04 Concierge,

G-12 Mail Room Pick Up, G-25 Party Room, G-25a Bar, G-51 Elevator Lobby – Wall



Specifications Page No.: 24

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.6 Stone Finishes: Marble Slab Con't.

MS-2 Supplier: SMDS

Contact: Sharon Allen (800)-361-3194 x235

Type: Quartz Slab
Colour/No.: K-Soul Gloss
Finish: Polished
Size: 34" Thick

Area No.: G-19 Men's Washroom, G-21 Women's Washroom,

G-30 Men's Change Room,

G-34 Women's Change Room - Countertop



Specifications Page No.: 25

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.7 <u>Vinyl Bases:</u>

VB-1 Supplier: Johnsonite

Contact: Tom Joyce (905) 886-8081 Series: Vinyl Cove Base 1/8" Colour/No.: Moon Rock / #29

Size: 4" High

Area No.: G-12a Mail Delivery, G-13 Mechanical Closet,

G-39 Electrical Closet, G-41 Garbage Staging Area, G-42 Bike Storage Area, G-43 Garbage Holding, G-44 Exit Vestibule, G-45 Townhouse Refuse Room,

G-46 Garbage Loading Area Bay,

G-47 Stair Exit Corridor 1, G-48 Stair Exit Corridor 2,

P-03, P2-03, P1-03 North Air Lock,

P-04, P2-04, P1-04 South Air Lock, P-05 Lockers, P-06 Ricycle Storage Room, P1-05 Corridor

P-06 Bicycle Storage Room, P1-05 Corridor, P1-06 Lockers, P1-07 Mechanical Room,

P1-08 Electrical Room 2, P1-09 Communication Room, P1-10 CCU Room, P1-11 Seasonal Furniture Storage,

P1-12 Electrical Room, P1-13 Garbage Room, P2-05 Lockers, P2-06 Bicycle Storage Room, P2-07 Mechanical Room, T-04 Electrical,

Stair A, B, C, D



Specifications Page No.: 26

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.8 Acoustical Ceiling Tile:

ACT-1 Supplier: Armstrong Ceilings

Contact: Sarah Withey (416) 525-0003
Type: Ultima Open Plan Tegular,

70% Recycled Content

No.: 1945

Edge Profile: Beveled Tegular Size: 24" x 48" x 34"

Tile Colour: White

Tee Grid: 9/16" Suprafine Exposed Tee Grid System

Grid Colour: White

Perimeter: #7873 Shadow Moulding

Smoke: 50 Flame: 25

Area No.: T-02 Suite Corridor – Refer to RCP

ACT-2 Supplier: Armstrong Ceilings

Contact: Sarah Withey (416) 525-0003

Type: Dune Tegular

35% Pre-Consumer Recycled Content 18% Post-Consumer Recycled Content

No.: 1724 HRC

Edge Profile: Beveled Tegular

Size: 24" x 24" Tile Colour: White

Tee Grid: 9/16" Suprafine Exposed Tee Grid System

Grid Colour: White

Perimeter: #7873 Shadow Moulding

Smoke: 50 Flame: 25

Area No.: G-06 Office Reception, G-07 Admin Office



Specifications Page No.: 27

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.8 Acoustical Ceiling Tile:

ACT-3 Supplier: Armstrong Ceilings

Contact: Sarah Withey (416) 525-0003

Type: Soundscapes Shapes Acoustical Clouds

70% Recycled Content

No.: 5441WH Convex / 5442WH Concave

Size: 4' x 4' x 7/8"

Panel Colour: White Accessory Colour: White

Installation Type: Grouping Frames

Smoke: 50 **Flame:** 25

Area No.: G-23 Exercise Room, G-24 Yoga Studio

ACT-4 Supplier: Laqfoil

Contact: Dimitriy Zarossilenok (416) 663-1708

Type: PVC Stretched Membrane

No.: #347

Panel Colour: High Gloss Black

Smoke: 110 Flame: 10

Area No.: G-16 Dining Room, G-25 Party Room



Specifications Page No.: 28

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

General Note:

- 1. Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID7-01 and relevant Elevations & Details prior to pricing.
- 2. Any proposed substitutions or modifications to the specifications require the Designer's approval.
- 3. Any discrepancies are to be brought to the Designer's attention prior to pricing/or ordering/or installation of any product.
- 4. Contractor must submit samples of all specified products prior to commencing work.

2.9 Wallcoverings:

W-1 Supplier: Metro Wallcoverings

Contact: Natasha Prowell (905) 738-5177 ext 7460

Book: Koroseal

Pattern: Patty Madden / Leda Colour/No.: Silver Satin / #L419-05

Width: 54/55"

Repeat: 52" H x 35.13" V / Non-Reverse Straight Match

Flame: 10 Smoke: 15

Area No.: G-05 Office Corridor, G-11 Corridor, G-12 Mail Pick Up,

G-15a Fover, G-17 Corridor, G-28 Fitness Studio Corridor,

G-29 Men's Vestibule, G-33 Women's Vestibule, G-51 Elevator Lobby, P-01, P2-01, P1-01 Vestibules,

P-02, P2-02, P1-02 Elevator Lobbies



Specifications Page No.: 29

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.9 Wallcoverings Con't.

W-2 Supplier: Metro Wallcoverings

Contact: Natasha Prowell (905) 738-5177 ext 7460

Book: Patty Madden Pattern: Ankara Vine

Colour/No.: Vali / LXB-AKV-08

Width: 52/54"

Repeat: 33" Vertical, 52" Horizontal, Straight Hang Random Match

Flame: 10 **Smoke:** 15

Area No.: G-16 Dining Room

W-3 Supplier: Crown Wallpaper

Contact: Diane Neville (416) 245-2900

Book: Symphony Pattern: Front Row

Colour/No.: Ore / # AZ52246FT

Width: 52"

Repeat: 18" H x 17.375" W / Straight hand match

Flame: 25 **Smoke:** 45

Area No.: G-25 Party Room, G25a Bar

W-4 Supplier: Crown Wallpaper

Contact: Diane Neville (416) 245-2900

Book: Symphony Pattern: Virtuoso

Colour/No.: Rhodium / # AZ52254VR

Width: 54"

Repeat: None / Reverse random match

Flame: 25 Smoke: 45

Area No.: G-06 Office Reception, G-07 Admin Office, G-09 Boardroom



Specifications Page No.: 30

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.9 Wallcoverings Con't.

W-5 Supplier: Crown Wallpaper

Contact: Diane Neville (416) 245-2900

Book: Versa

Pattern: Wavelengths

Colour/No.: Char / # A115-344

Width: 52/54"

Repeat: None / Reverse Hang, Straight Across Match

Flame: 5 Smoke: 20

Area No.: G-23 Exercise Room, G-24 Yoga Studio (Main)

W-6 Supplier: Levey Wallcoverings

Contact: Jed Burrows (905) 829-8000

Book: Cirqa

Pattern/No.: Lucy in the Sky / # Levey11 - 005398

Colour/No.: Inner Light / # Q48-493

Width: 52/54"
Repeat: 24" V
Flame: 10
Smoke: 20

Area No.: G-23 Exercise Room, G-24 Yoga Studio, G-27 Fitness Foyer

(Accent)



Specifications Page No.: 31

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.9 Wallcoverings Con't.

W-7 Supplier: Crown Wallpaper

Contact: Diane Neville (416) 245-2900

Book: Tri-Kes
Pattern: Bankwire

Colour/No.: Dove / # 2VBN-13

Width: 54"

Repeat: None / Reverse Hang, Random Match

Flame: 5 Smoke: 20

Area No.: G-19 Men's Washroom, G-21 Women's Washroom,

G-50 Guest Suite

W-8 Supplier: Crown Wallpaper

Contact: Diane Neville (416) 245-2900

Book: Symphony Pattern: Singer

Colour/No.: Chromatic Crescendo / # AZ52418SG

Width: 54"

Repeat: 18" H x 54"W / Reverse Random Match

Flame: 25 **Smoke:** 45

Area No.: T-01 Elevator Lobby, T-02 Suite Corridor



Specifications Page No.: 32

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details prior to pricing.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-1 Supplier: ICI Paints

Series: Xpert #47010 Series Latex Concrete Floor Paint Colour/No.: Grey Tweed / #30YY 22/059 (Order #A1839)

Finish: As per Builder's Standard

W/Base: VB-1

Area No.: G-12a Mail Delivery, G-13 Mechanical Closet,

G-39 Electrical Closet, G-41 Garbage Staging Area, G-42 Bike Storage Area, G-43 Garbage Holding, G-44 Exit Vestibule, G-45 Townhouse Refuse Room,

G-46 Garbage Loading Area Bay,

G-47 Stair Exit Corridor 1, G-48 Stair Exit Corridor 2,

P-03, P2-03, P1-03 North Air Lock,

P-04, P2-04, P1-04 South Air Lock, P-05 Lockers, P-06 Bicycle Storage Room, P1-05 Corridor,

P1-06 Lockers, P1-07 Mechanical Room,

P1-08 Electrical Room 2, P1-09 Communication Room, P1-10 CCU Room, P1-11 Seasonal Furniture Storage,

P1-12 Electrical Room, P1-13 Garbage Room, P2-05 Lockers, P2-06 Bicycle Storage Room, P2-07 Mechanical Room, T-04 Electrical,

Stair A, B, C, D - Floor



Specifications Page No.: 33

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints Con't:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details prior to pricing.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-2 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Pewter Grey / #50YY 47/053 (Order #A1857)

Finish: Eggshell #59311 or Semi–Gloss #59211
- Applicable as per Builder's Standard -

Area No.: G-03 CACF, G-08 Servery, G-10 Storage, G-12a Mail Delivery,

G-13 Mechanical Closet, G-22 W.I.C.

G-26 Party Room Servery, G-39 Electrical Closet,

G-40 Loading Area Airlock, G-41 Garbage Staging Area,

G-42 Bike Storage Area, G-43 Garbage Holding, G-44 Exit Vestibule, G-45 Townhouse Refuse Room,

G-46 Garbage Loading Area Bay,

G-47 Stair Exit Corridor 1, G-48 Stair Exit Corridor 2, G-49 Moving Room, P-03, P2-03, P1-03 North Air Lock,

P-04, P2-04, P1-04 South Air Lock, P-05 Lockers, P-06 Bicycle Storage Room, P1-05 Corridor,

P1-06 Lockers, P1-07 Mechanical Room,

P1-08 Electrical Room 2, P1-09 Communication Room,

P1-10 CCU Room, P1-11 Seasonal Furniture Storage,

P1-12 Electrical Room, P1-13 Garbage Room, P2-05 Lockers, P2-06 Bicycle Storage Room, P2-07 Mechanical Room, T-04 Electrical,

Stair A, B, C, D - Wall



Specifications Page No.: 34

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints Con't:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details prior to pricing.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-3 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: White on White / # 30GY 88/014 (Order #A0148)

Finish: Flat #59111

Area No.: All ceilings throughout unless otherwise denoted

P-4 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Forest Black / #30YY 10/038 (Order #A1833)
Finish: Semi-Gloss-#59211 (for metal application) or
High Gloss Factory Applied Spray Paint

Area No.: Ground Floor Redi-frames & Hollow Metal frames adjacent

to Finish PL-4 or S-3 (Semi-Gloss)

G-16 Dining Room – Metal Decorative Screen at FCU doors

(Factory Applied Spray Paint)

Note: <u>Final colour to be confirmed by Designer once sample of Stain S-3 is</u> provided.

P-5 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Toasty Grey / # 30YY 51/098 (Order #A1851)

Finish: Flat #59111

Area No.: G-30 Men's Change Room, G-34 Women's Change Room -

Doors & Ceiling



Specifications Page No.: 35

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints Con't:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details <u>prior to pricing</u>.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-6 - Same as P-1 -

Finish: Flat #59111 or High Gloss

Area No.: G-04 Concierge – Drywall niche behind pin mounted signage

in High Gloss Finish

G-23 Exercise Room, G-24 Yoga Studio,

G-27 Fitness Studio Foyer – Ceiling in Flat Finish

P-7 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Jefferson House / # 30YY 47/145 (Order #A1810)

Finish: Semi–Gloss #59211

Area No.: G-23 Exercise Room, G-24 Yoga Studio – Base & Trim

P-8 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Obilisk #20YY 45/114 (Order #A1797)

Finish: Semi–Gloss #59211

Area No.: T-01 Elevator Lobby, T-02 Suite Corridor – All Metal Doors &

Frames, FHC



Specifications Page No.: 36

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints Con't:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details prior to pricing.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-9 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: To match wall or ceiling finish adjacent to metal grill, provide

paint draw-downs for Designer's approval

Finish: Semi-Gloss-#59211 (for metal application)

Area No.: All paint grade metal air and mechanical grills in walls

throughout, unless otherwise noted.

P-10 - Same as P-1 -

Finish: Semi–Gloss #59211 (for metal application)

Area No.: Ground & Penthouse Floor – All Metal Doors & Frames, FHC

Stairs A, B, C, D - Metal Railings, Pickets, Metal Doors &

Frames - Stairwell side only

P-11 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Obilisk #20YY 45/114 (Order #A1797)

Finish: Semi–Gloss #59211

Area No.: T-01 Elevator Lobby, T-02 Suite Corridor – Baseboards &

Casings

Note: Complete suite entry mock up to be approved by Designer prior to painting throughout.



Specifications Page No.: 37

Project No. 11-302 **Project: Argento Condo**

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 **Paints Con't:**

General Note:

- Contractor must verify all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & **Details prior to pricing.**

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-12 **Supplier: ICI Paints**

> **Series: Life Master (Low VOC Content)**

Colour/No.: Skyline / #70BB 65/066 (Order #A1507)

Finish: **Eggshell #59311**

G-50 Guest Suite Washroom - Wall Area No.:

P-13 Supplier: **ICI Paints**

> **Series: Life Master (Low VOC Content)**

Colour/No.: Antique White RM / #43YY 78/053 (Order #A0065)

Finish: **Semi-Gloss #59211**

T-01 Elevator Lobby, T-02 Suite Corridor – Frieze Moulding Area No.:

P-14 Supplier: **Para Paints**

> **Series: Essence (Zero VOC Content)** Colour/No.: Pump Fever #P5192-85D Finish: **Semi-Gloss #59211**

T-01 Elevator Lobby – Elevator Doors, Frames & Door Header 1st-25th Floors Area No.:



Specifications Page No.: 38

Project: Argento Condo Project No. 11-302

Section 2.0

Wall, Ceiling and Floor Finishes

2.10 Paints Con't:

General Note:

- Contractor <u>must verify</u> all denoted Finishes Locations/Areas in these Specifications with the Room Finish Schedule ID-7-01 and relevant ID Elevations & Details <u>prior to pricing</u>.

- Provide Paint Draw-Downs of each specified Paint/Finish for Designer's approval.

P-15 - Same as P-2 -

Finish: Semi–Gloss #59211 (for metal application)

Area No.: Parking Levels P4 to P-1 – All Metal Doors & Frames, FHC

P-16 Supplier: Benjamin Moore

Colour/No.: Super Nova / # CC-990

Finish: Eggshell or Flat as applicable

Area No.: G-15 Theatre - Wall, Trim & Base (Eggshell)

- Ceiling (Flat)

P-17 Supplier: ICI Paints

Series: Life Master (Low VOC Content)

Colour/No.: Forest Black / #30YY 10/038 (Order #A1833) Finish: Semi-Gloss-#59211 (for metal application)

Area No.: T-01 Elevator Lobby, T-02 Suite Corridor Ground Floor

Redi-frames adjacent to Finish S-3 (Semi-Gloss)

Note: <u>Final colour to be confirmed by Designer once sample of Stain S-3 is provided.</u>



Specifications Page No.: 39

Project: Argento Condo Project No. 11-302

Section 3.0 Metals

3.0 Metals

3.1 General Notes

- 1. Refer to Floor Finishes, Millwork Details and Elevations for locations of metal inlays, finishes, etc.
- 2. Contractor to verify site conditions and dimensions prior to ordering and installation of materials.
- 3. Designer must approve actual sample of metal finishes prior to ordering.
- 4. Miter and polish all joints of metal inlays.
- 5. Application of metals to follow faithfully the highest industry standards.

3.2 Finishes

M-1 1/2" Stainless Steel Floor Inlay

Supplier: *Schluter Systems (Canada) Inc.

Contact: Joanna Tiffin 647-225-8844

Type: Quadec

- 1. Description: profile with 1/2 inch (12.5 mm) wide visible surface and integrated trapezoid-perforated anchoring leg. Q 125 E
- 2. Anchoring Leg:
 - a. Provide with straight anchoring leg
- 3. Material and Finish:
 - a. E Stainless Steel Type 304 = V2A.
 - 1) Height as required.

Area No.: - Refer to Floor Finishes Plans & Room Schedule -

<u>Note:</u> All metal inlays in floors must be installed flush with adjacent floor finishes, and mitered at corners and intersections.



Specifications Page No.: 40

Project: Argento Condo Project No. 11-302

Section 4.0 Plastic Laminates

4.1 General Notes

1.1 Refer to millwork details for location of surfaces for plastic laminate finish.

- 1.2 Application of plastic laminates shall follow faithfully the highest industry standards and procedures.
- 1.3 Alternatives to plastic laminate are to be approved by the Designer before commencement of work.
- 1.4 Refer to Section 6.0 Millwork for additional notes.

4.2 Finishes

PL-1 Supplier: Mercury Wood

Series: I.T Series / Thermo-Fused Melamine Contact: Kevin Humphries (416) 747-1163

Colour/No.: Rovere Tasso / # Frati-02

Finish: Poro Arioso

Size: Sheet Size 9'-3" L x 6'-1" W x 3/4" Thick

Edge: Frati 02D / Rovere Tasso

Area No.: G-01 Vestibule, G-02 Lobby, G-51 Elevator Lobby

- Wall & Ceiling

G-16 Dining Room – Wall

PL-2 Supplier: Pionite

Series: Plastic Laminates Colour/No.: Ice Fishin / # WF181

Finish: Suede

Area No.: G-04 Concierge - Millwork (all interior surfaces to

receive Melamine to match) G-12 Mail Pick-Up – Countertop



Specifications Page No.: 41

Project: Argento Condo Project No. 11-302

Section 4.0 Plastic Laminates

4.2 Finishes Con't

PL-3 Supplier: Abet Corporation

Series: Plastic Laminates Colour/No.: Silver / #2704

Finish: N/A

Area No.: G-30 Men's Change Room,

G-34 Women's Change Room – Wall & Ceiling

PL-4 Supplier: Mercury Wood

Series: I.T Series / High Pressure Plastic Laminate

Contact: Kevin Humphries (416) 747-1163

Colour/No.: Rovere Tasso / # Frati-02B

Finish: Poro Arioso

Area No.: Gnd. Floor CACF Door -Refer to Door Schedule ID8.01

PL-5 Supplier: Octopus

Series: Octolam

Colour/No.: Mirror Chrome / #880

Finish: N/A

Area No.: G-02 Lobby – Wall

G-25a Bar - Wall



Specifications Page No.: 42

Project: Argento Condo Project No. 11-302

Section 4.0 Plastic Laminates

4.2 Finishes Con't

PL-6 Supplier: Pionite

Series: Plastic Laminates

Colour/No.: Negotiating in Geneva / # PFA60

Finish: Suede

Area No.: G-25a Bar – Millwork (all interior surfaces to

receive Melamine to match)

PL-7 Supplier: Formica

Series: Plastic Laminates

Colour/No.: Aluminum Twirl / #5396

Finish: N/A

Area No.: G-23 Exercise Room, G-24 Yoga Studio

- Mirror Frame

PL-8 Supplier: Octopus

Series: Octolam

Colour/No.: Natural Allusion / #196

Finish: N/A

Area No.: G-15 Theatre – Millwork (all interior surfaces to

receive Melamine to match)

PL-9 Supplier: Arborite

Series: High Pressure Laminate Colour/No.: Tatami Nezumi / #P-124.SR

Finish: SR - Structured

Area No.: Elevator Cabs - # 1, 2, 3 – Wall Panels

NOTE: Elevator Cab Laminate to be ordered

with Fire Rating



Specifications Page No.: 43

Project: Argento Condo Project No. 11-302

Section 5.0 Woods and Veneers

5.1 General Notes

- 1. Refer to Millwork Details, Elevations, Room and Door Finish Schedule for location of finishes.
- 2. Contractor to verify site conditions and dimensions prior to ordering and installation of materials.
- 3. <u>All</u> wood solids and veneers to be fire-rated as necessary to meet all Building Code and Fire Code Regulations.
- 4. Provide adequate blocking and reinforcing in walls where millwork, fixtures and equipment are to be installed.
- 5. Application of wood stains to follow faithfully the highest industry standards and procedures.
- 6. Finish on all stained wood to be low luster satin stain, unless otherwise noted.
- 7. Detailed shop drawings and graining diagrams (indicating direction of wood grain) for wood walls and millwork must be submitted to the Designer for approval prior to commencement of any work.
- 8. All woods, veneers and graining to be approved by Designer prior to ordering.
- 9. Refer to Section 6.0 Millwork for additional notes.

5.2 Finishes

S-1 Supplier: Tabu Veneers

Species: Birch Code: 73.049LFF

Area No.: G-25 Party Room

- Refer to Door & Room Schedule and relevant

Elevations & Details



Specifications Page No.: 44

Project: Argento Condo Project No. 11-302

Section 5.0 Woods and Veneers

5.2 Finishes Con't.

S-2 DELETE

S-3 Wood Stain on Solid Rift Cut Oak or Rift Cut Oak Veneer

Stain Colour: To match Plastic Laminate PL-1

Submit sample to Designer for approval prior to ordering

Area No.: Ground Floor Amenity Doors – Typical

T-02 Suite Corridor – Suite Entry Door & Header - Refer to Door & Room Schedule and relevant

Elevations & Details



Specifications Page No.: 45

Project: Argento Condo Project No. 11-302

Section 6.0 Millwork

6.1 General Notes & Instructions

- 1. Comply with general instructions and all documents referred to therein.
- 2. Provide all labor, materials product, equipment and services to complete the finish carpentry necessary and/or indicated on the drawings and specified herein.
- 3. Check all job site dimensions and conditions and notify the Designer in writing of unacceptable conditions. Do not proceed until remedial instructions are received.
- 4. Unless otherwise specified herein, comply with the requirements for premium grade work as set out in the quality standards for architectural millwork published by the AWMAC.
- 5. Submit shop drawings for all millwork items with sections, related elevations, and joinery details. Indicate direction of wood grain, veneer, gables and seams, etc.
- 6. Show details of fixing and joining, where methods indicated by the Designer can be improved upon, show such changes but maintain Designer's lines, levels and profiles.
- 7. Plywood:

Veneer core birch or oak plywood, depending on location; shop grade thickness as specified, for painted, or stained millwork.

- 8. Particle Board:
 - Core material for plastic laminate work shall be high density to thickness specified.
- 9. Co-ordinate with other trades to complete work, Do all cutting required for interface with mechanical, electrical and plumbing trades.



Specifications Page No.: 46

Project: Argento Condo Project No. 11-302

Section 6.0 Millwork

10. Where laminate must be seamed, provide flush and tight hairline joints. Where sections of plastic laminate clad millwork must be joined, make joints with blind splines and concealed draw bolts.

- 11. Supply and install all necessary wood blocking and /or plywood as required to ensure safe and stable construction.
- 12. All exterior exposed surfaces, including exposed gables, both sides of doors and drawer fronts to receive finish as specified for exterior of millwork unit; all interior exposed surfaces to receive melamine finish; colour to be approved by the Designer.
- 13. All coat closet hat shelves and exposed wood framing for paint finish to match wall finish in adjacent area, unless otherwise noted.
- 14. All coat closets to receive coat rod.
- 15. Provide full extension drawer glides; sides, backs and bottom of drawers to be $\frac{1}{2}$ " particle board.
- 16. All drawers and cupboard doors to have finger pulls.
- 17. All doors to have fully concealed hinges touch latch and magnetic catches, unless otherwise noted.
- 18. All shelves to be fully adjustable on flush recessed pilaster strips; colour: brushed silver.
- 19. Detail drawings not to be scaled.

- END OF SPECIFICATIONS -

RESIDENCES AT ARGENTO INC. 18 GRAYDON HALL DRIVE JOB NO. 2006-09

SCOPE OF WORK


ACTIVITY NAME: CORNICE MOULDING ACTIVITY NUMBER: 09400


The following list must be part of the Contractor's Scope of Work. However this list is to be used as a minimum guide and does not alleviate the Contractor of the responsibility to also carry out, in addition, other work according to the conventional good and current trade practices.

- 1. Contractor acknowledges that the plans and specifications are in some respects not complete. Contractor agrees that it will perform all cornice moulding work required, in accordance with the spirit and intent of these plans and specifications and to conventional and good trade practices, at no extra charge, even if not specifically reflected in the plans and specifications. This Contractor shall also fulfill all requirements of the Ontario Building Code and of all authorities having jurisdiction, at no expense to the Owner. Furthermore, the Contractor acknowledges the Owners intent to pursue LEED certification by the Canada Green Building Council and consents to make commercial best efforts to assist in this regard on all relevant LEED credits as mentioned below.
- 2. Contractor to supply all labour, materials, supervision, tools, tackle, equipment, transport, taxes, insurance, etc., necessary to carry out and complete the Contractor's work in all areas on the above project as outlined here in.
- 3. This Contractor to provide sufficient equipment, labour and materials to maintain Owner's Construction Schedule as attached in **Schedule "D"** dated August 30, 2014 and which may be amended from time to time by the Construction Manager. Contractor to maintain sufficient stock of materials to complete entire building requirements. **It is anticipated that the installation of the Lobby Cornice Moulding will start in and around February 2015.**
- 4. This Contractor shall be responsible for daily cleaning relative to his work and deposit his garbage in the garbage container provided by Owner. It is this Contractor's responsibility to leave each room area broom-swept. Failure to comply will result in an automatic back-charge without notice.
- 5. This Contractor acknowledges the Owners intent to reduce construction waste shipments to landfill sites, and will review and comply with the sites construction waste management plan, which seeks to achieve a 75% diversion rate.
- 6. This Contractor may be required to have a representative present for all construction site meetings (usually bi-weekly) prior to and during his on site work to help coordinate this Contractor's work with all other contractors on site. The representative is expected to record and periodically submit relevant documentation to the Owner as it relates to each referenced LEED credit.

Common Areas

7. This Contractor to supply and install custom plaster moulding to all common area corridors and elevator lobbies as shown on the Interior Design Drawings and as referenced on ID6.17 and ID9.01 (**Details #9 and #10**). Paint finish by others.





8. This Contractor is advised all wood crown moulding/frieze (stained or veneered) i.e. for the Ground Floor Party Room and Dining Room, will be supplied and installed by the Finishing Carpenter.

9. Contractor is advised that this project is "sprinklered" throughout with both downward facing and sidewall concealed heads. All efforts have been made by the Designer and Owner to avoid sprinkler head collisions with crown moulding runs; however Contractor to note that periodic breaks may be required for the Residential Corridors on 2nd, 10th, 13th, 18th and PH floors where T-Bar ceiling is installed. Contractor to refer to ceiling cross sections on ID6.17.

In-Suite Finishes

- 10. This Contractor shall supply and install 6" plaster cornice moulding in the front entrance foyer, living room, dining room, kitchen and breakfast area for the 9 Townhomes as per all Drawings and Specifications. Please Note: Cornice moulding is not a "Standard" finish inside the suites of the Condo Tower; this Contractor may be asked to install 6" or 7" moulding as an "Upgrade" only.
- 11. This Contractor to coordinate his work with the Site Supervisor so that all in-suite cornice moulding is installed prior to ceiling spray stucco (to ensure a smooth straight border between cornice and stucco). Total protection of surrounding areas and materials must be provided by this Contractor.
- 12. **TOWER-** All in-suite ceilings shall receive a stippled textured ceiling, including the kitchen area, with the exception of those areas featuring a dropped drywall ceiling i.e. bathrooms, closets, and the PH Level, which shall be finished "smooth". **Please Note:** Penthouse suites shall receive smooth ceilings throughout.

	In-Suite Ceiling Height	Door Height	Bathroom Ceiling Height	Baseboard/Casing (Step Bevel)
Ground	8'-6"	6'-8"	8'-6"	5" / 3"
2 nd	9'	7'	8'	5" / 3"
3-9	8'-6"	6'-8"	7'-6"	5" / 3"
10-27	9'	7'	8'	5" / 3"
PH	10'	8'	9'	5" / 3"

13. **TOWNHOUSES**- The entire main floor level of <u>each</u> Townhouse Unit shall receive a smooth ceiling. 2nd Level & 3rd level floors (containing the bedrooms) shall receive a sprayed textured finish by the Drywall Contractor. All bathrooms and closets shall feature a smooth dropped ceiling.

Purchaser Upgrades

- 14. This Contractor will be required, where requested, to carry out **Purchaser Upgrades** (Purchaser Agreements) at a pre-determined cost. Cost includes all overhead and profit and will reflect the final total invoice cost for each item on an individual basis.
- 15. It is this Contractor's responsibility to visit the site office prior to commencing work in a suite to pick up all accepted Work Orders (purchaser upgrades) and all associated specifications and black-lines.
- 16. Where requested, this Contractor to supply and install in-suite plaster moulding upgrades (for the Tower and Townhomes- 2nd & 3rd floors) at an extra to contract unit rate of <u>\$7</u> per linear foot for 6" mouldings and **\$7.50** per linear foot for 7" mouldings.

Deficiencies

- 17. Supply and install all cornice moulding with proper flush mitred joints at all corners and angles. Straight sections to be done without any visible joints. All cracks caused by shrinkage will be repaired by this Contractor.
- 18. This Contractor shall report to the Site Supervisor any defects to background surfaces prior to commencement of his work on these surfaces. If this Contractor does not report any defects, he will assume any and all responsibility to rectify his work, should the work not be deemed acceptable by the Site Supervisor and the Purchaser.

Job Specific

- 19. This Contractor is to refer to attached **Schedules "B"** for "Features and Finishes" of the Townhouse Units (only). Cornice moulding is not an included feature for the Condo Tower suites.
- 20. This Contractor shall supply and install all cornice work for the Common Areas as per the Interior Design Drawings and Finishes Specifications Manual dated March 26, 14 attached as **Schedule 'E'**.
- 21. This Contractor is responsible to make all deliveries as per the instructions of the Site Supervisor. A Dual Hoist shall be provided for the Tower during construction to facilitate loading and hoisting of materials.

- 22. This Contractor shall be responsible for hoisting (hand bombing) all material inside the **Townhomes** as <u>no</u> formal hoist will be installed by the Owner.
- 23. Contractor to adhere to VOC Limits for Adhesives and Sealants as they appear in the attached **Schedule 'F'**.
- 24. This Contractor has been advised that there will be **no on-site parking** provided at any stage of construction of this project. Limited Parking may be available through the neighboring Property Manager for a monthly fee.

LEED REQUIREMENTS

- 1) The Contractor acknowledges the Owner's intent to achieve a <u>LEED</u> green building rating for this project from the Canada Green Building Council and that the following LEED credits are relevant to this scope of work. Some of the following credits require additional documentation and verification by the Contractor. While not expected to provide the final LEED submissions, the Contractor's work and supplies will make important contributions to success with LEED. Therefore, the Contractor is expected to pay special attention to documentation of deliveries to/from the site and various relevant materials applications.
- 2) LEED refers to the Leadership in Energy and Environmental Design, a green building rating program administered by the Canada Green Building Council.
- 3) List of LEED credits related to this scope of work: Materials & Resources Credit 2.1 & 2.2: Construction Waste Management Objective: Divert demolition and construction waste from landfill by at least 75% in aggregate

Materials & Resources Credit 4.1 & 4.2: Recycled Content

Objective: Increase the use of post-consumer and post-industrial recycled content in materials supplied to the project

Materials & Resources Credit 5.1 & 5.2: Regional Materials

Objective: Increase the use of building materials and products that are processed and manufactured within 800 km of the job site (or 2400 km if shipped by rail or water)

Indoor Environmental Quality 4.1: Low-Emitting Materials – Adhesives & Sealants

Objective: To use adhesives and sealants that meet the requirements listed in the IEQ

Management Plan

Indoor Environmental Quality 4.2: Low Emitting Materials – Paints & Coatings Objective: To use paints & coatings that comply with the Green Seal and/or SCAQMD standards as stated in the IEQ Management Plan

More detailed information on the above listed credits can be found on the Canada Green Building Council's website: www.cagbc.org or can be requested from the Owner directly.

Aug.30th.13			truction Scheo																								
Aug.30(11.13		ADDII	Argento	OKO																		715 Days			(less 2 lost days/	mth)	-
	FORMING P A			•																1st Floor Occup	pancy	38.3		Months	s 1st Occupanc	У]
	700 70			Sultes Floors		320 28									Dravalle	starts at 1	tho End				Г	823 Days	_				
Install Elevator	631			derground	ı	4	Therefor	10710001	110	Working Days]				Oth Floor				Last Floor Occu	<i>upancy</i>	43.3		Months	Last Occupano	у]
	630 5			Elevators Masonry		14 1	Weeks = 1 = Yes		Working Days lasonry buildin	ng, Masonry will	start at the	e End of	f the 6th Floor F	orming							ſ	434 Days	П				
Elevator Power	626 625			Precast	ERIOR &	0	0 = No	_	recast building	g, Precast will st	art at the I	End of th	ne 7th Floor Fo		MIM			Granite		Undergrous	nd	23.3 SHITE		Months	to Ground Floo	r]
Main	25	MASONRY	WINDOWS	CORRID	ORWALLS	CHAN	NEL HVAC &	ELECT.	Fir Lvi	DRYWALL		APE	& PRIME	& B	ASE	TILI	KITOTILNO	Tops	s PAINT	ELECT.	Hard	wood CLEAN	Days	irbi	Inspec	Occupancy	4
Roof	601 600	P A	P A 687	<u>Р</u> 692	Α	Р 717	A P 722	Α	P A 727	737 A	742	Α	P A	P 752	Α	P 757	A P A 762	767	A P A	777 A	782	A P A 786		P A 791	P A 808	P 823	
28th	4		5	5		5	5		5	5	5		5	5		5	5	5	5	5	5	4		4	4	4	28th
10 units	597 596		683 682	688 687		713 712	718 717		723 722	733 732	738 737		743 742	748 747		753 752	758 757	763 762	768 767	773 772	778 777	783 781	- 5	788 787	805 804	820 819	10 units
27th	4		5	5		5	5		5	5	5		5	5		5	5	5	5	5	5	4	,	4	4	4	27th
IU UNITS	593 592		678 677	683 682		708 707	713 712		718 717	728 727	733 732		738 737	743 742		748 747	753 752	758 757	763 762	768 767	773 772	778 776	6	784 783	801 800	816 815	IU UNITS
26th 10 units	4 589		5 673	5 678	$+ \exists$	5 703	5 708		5 713	5 723	5 728		5 733	5 738		5 743	5 748	5 753	5 758	5 763	5 768	773	7	4 780	797	812	26th 10 units
	588		672	677		702	707		712	722	727		732	737		742	747	752	757	762	767	771		779	796	811	
25th 10 units	4 585		5 668	673	+ +	5 698	5 703		5 708	5 718	723		5 728	733		5 738	5 743	748	753	5 758	5 763	768	8	4 776	793	808	25th 10 units
	584		667	672		697	702		707	717	722		727	732		737	742	747	752	757	762	766		775	792	807	
24th 10 units	4 581		5 663	5 668		5 693	5 698		5 703	5 713	718		5 723	5 728		5 733	5 738	743	748	5 753	5 758	4 763	9	772	789	4 804	24th 10 units
23rd	580 4		662 5	667 5		692 5	697 5		702 5	712	717 5		722	727 5		732 5	737 5	742 5	747 5	752 5	757 5	761 4		771 4	788 4	803 4	2254
2310 10 units	577		658	663		688	693		698	5 708	713		718	723		728	733	738	743	748	753	758	10	768	785	800	23rd 10 units
22nd	576 4		657 5	662 5		687 5	692 5		697 5	707 5	712 5		717 5	722 5		727 5	732 5	737	742 5	747 5	752 5	756 4		768 4	784	799 4	22nd
10 units	573		653	658		683	688		693	703	708		713	718		723	728	733	738	743	748	753	12	765	781	796	10 units
21st	572 4		652 5	657 5		682 5	687 5		692 5	702 5	707 5		712 5	717 5		722 5	727 5	732	737 5	742 5	747 5	751 4		764 4	780 4	795 4	21st
12 units	569		648	653		678	683		688	698	703		708	713		718	723	728	733	738	743	748	13	761	777	792	12 units
20th	568 4		647 5	652 5		677 5	682 5		687 5	697 5	702 5		707 5	712 5		717 5	722 5	727 5	732 5	737 5	742 5	746 4		760 4	776	791 4	20th
12 units	565		643 642	648 647		673	678 677		683	693 692	698 697		703 702	708 707		713 712	718 717	723	728 727	733	738 737	743 741	14	757	773	788 787	12 units
19th	564 4		5	5		672 5	5		682 5	5	5		5	5		5	5	722 5	5	732 5	5	4		756 4	772 4	4	19th
12 units	561 560		638 637	643 642		668 667	673 672		678 677	688 687	693 692		698 697	703 702		708 707	713 712	718 717	723 722	728 727	733 732	738 736	15	753 752	769 768	784 783	12 units
18th	4		5	5		5	5		5	5	5		5	5		5	5	5	5	5	5	4		4	4	4	18th
12 units	557 556		633 632	638 637		663 662	668 667		673 672	683 682	688 687	-	693 692	698 697		703 702	708 707	713 712	718 717	723 722	728 727	733 731	16	749 748	765 764	780 779	12 units
17th	4		5	5		5	5		5	5	5		5	5		5	5	5	5	5	5	4		4	4	4	17th
12 units	553 552		628 627	633 632		658 657	663 662		668 667	678 677	683 682		688 687	693 692		698 697	703 702	708 707	713 712	718 717	723 722	728 726	17	745 744	761 760	776 775	12 units
16th 12 units	4 549		5 623	5 628		5 653	5 658		5 663	5 673	5 678		5 683	5 688		5 693	5 698	5 703	5 708	5 713	5 718	723	18	4 741	4 757	4 772	16th
	548		622	627		652	657		662	672	677		682	687		692	697	702	707	712	717	721	18	740	756	771	12 dints
15th 12 units	4 545		5 618	623	1	5 648	5 653		5 658	5 668	5 673		5 678	5 683		5 688	5 693	5 698	5 703	5 708	5 713	718	19	737	753	4 768	15th
	544		617	622		647	652		657	667	672		677	682		687	692	697	702	707	712	716	17	736	752	767	12 011113
14th 12 units	4 541		5 613	5 618	+ -	5 643	5 648		653	663	5 668		5 673	5 678		5 683	5 688	693	698	5 703	5 708	713	20	733	749	764	14th 12 units
	540		612	617		642	647		652	662	667		672	677		682	687	692	697	702	707	711		733	748	763	12 dillio
13th 12 units	537		5 608	5 613	1	5 638	5 643		5 648	5 658	5 663		668	673		5 678	5 683	5 688	693	5 698	5 703	708	22	730	745	760	13th 12 units
1045	536		607	612		637	642		647 5	657	662		667	672		677	682	687	692	697	702	706		729	744	759 4	1046
12th 12 units	533		603	608		5 633	5 638		643	5 653	5 658		663	668		5 673	678	683	688	5 693	5 698	703	23	726	741	756	12th 12 units
11th	532		602 5	607 5		632 5	637 5		642 5	652 5	657 5		662 5	667 5		672 5	677 5	682 5	687 5	692 5	697 5	701 4		725 4	740 4	755 4	11th
12 units	529		598	603		628	633		638	648	653		658	663		668	673	678	683	688	693	698	24	722	737	752	12 units
10th	528 4		597 5	602 5	1	627 5	632 5		637 5	647 5	652 5		657 5	662 5		667 5	672 5	677 5	682 5	687 5	692 5	696		721 4	736	751 4	10th
12 units	525		593	598		623	628		633	643	648		653	658		663	668	673	678	683	688	693	25	718	733	748	12 units
	524		592	597		622	627		632	642	647		652	657		662	667	672	677	682	687	691		717	732	747	_

9th	4		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	9th
12 units	521		588	593	618	623	628	638	643	648		653	658	663	6	668	673	678	68	3	688		26	714	729	744	12 units
	520		587	592	617	622	627	637	642	647		652	657	662	- 6	67	672	677	68	2	686			713	728	743	
8th	4		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	8th
12 units	517		583	588	613	618	623	633	638	643		648	653	658	6	663	668	673	67	8	683		27	710	725	740	12 units
	516		582	587	612	617	622	632	637	642		647	652	657	6	62	667	672	67	7	681			709	724	739	
7th	4		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	7th
12 units	513		578	583	608	613	618	628	633	638		643	648	653	6	558	663	668	67	3	678		28	706	721	736	12 units
	512		577	582	607	612	617	627	632	637		642	647	652	- 6	557	662	667	67	2	676			705	720	735	
6th	4		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	6th
12 units	509		573	578	603	608	613	623	628	633		638	643	648	- (553	658	663	66	8	673		29	702	717	732	12 units
	508		572	577	602	607	612	622	627	632		637	642	647	- 6	552	657	662	66	7	671			701	716	731	
5th	6		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	5th
12 units	503		568	573	598	603	608	618	623	628		633	638	643	- 6	48	653	658	66	3	668		30	698	713	728	12 units
	502		567	572	597	602	607	617	622	627		632	637	642	6	47	652	657	66	2	666			697	712	727	
4th	8		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	4th
12 units	495		563	568	593	598	603	613	618	623		628	633	638	- 6	643	648	653	65	8	663		31	694	709	724	12 units
	494		562	567	592	597	602	612	617	622		627	632	637	- 6	642	647	652	65	7	661			693	708	723	_
3rd	15		5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	3rd
12 units	480		558	563	588	593	598	608	613	618		623	628	633	- (38	643	648	65	3	658		32	690	705	720	12 units
	479	542	557	562	587	592	597	607	612	617		622	627	632	- (37	642	647	65	2	656			689	704	719	
2nd	20	15	5	5	5	5	5	5	5	5		5	5	5		5	5	5	5		4			4	4	4	2nd
11 units	460	528	553	558	583	588	593	603	608	613		618	623	628	- (33	638	643	64	8	653		33	686	701	716	11 units
	459	527	552	557	582	587	592	602	607	612		617	622	627	- 6	32	637	642	64	7	648			685	700	715	
Ground	25	15	10	5	5	5	5	5	5	5		5	5	5		5	5	5	5		1			1	1	11	Ground
1 unit	435	513	543	553	578	583	588	598	603	608		613	618	623	- 6	28	633	638	64	3	648		37	685	700	715	1 unit
	FORMING	MASONRY	WINDOWS	EXTERIOR	& CHANNEL	ROUGH PLUMB.	Fir Lvi	DRYWALL	TAPE	SPRAY	CEIL.	TRIM	TIL	E KITCHE	ENS	Granite	- 1	PAINT	INISH	Hardwood	SUIT	E		IPDI	Owner	Occupancy	
				CORRIDOR W	ALLS	HVAC & ELECT.				& PR	IME	& BASE				Tops		P	LUMB.		CLE	N.	Days		Inspec		

Recreation Center

ſ		- 5	72	582		602		617	622	627	637	6	42	657	662	672	677	682	687	692	693
	Ground	-	15	10		20		15	5	5	10		5	15	5	10	5	5	5	5	1
		5	58	573		583		603	618	623	628	6	38	643	658	663	673	678	683	688	693
-			CHANNEL	ROU	IGH	DRYWA	.L	TAPE	SPRAY	Floor LvI	Tile)	Kitchens	Millwark	Trim &	PAINT	FINISH	CARPET	Clean &	CONST	Occup
				PLU	мв				CEIL.						Base		PLUMB.		Furnitture	INSPEC	
				ELE	~~				& PRIME							_	ELECT.				_

Underground

		ung avation		sours Suffrees		tackfill	FU	xii iyo	-	3.0	FO	aau	FZ	Jau		a au	Garay	jeruu
	G,	arina	Col	ssons	Our Ev	cavation	Eo	otinas	DA	30G	Da	Slab	Da	Slab	P1	Cloh	Coron	e Roof
Levels	11	11	304		349		369		389		399		409		419		434	
P4 - P1 Garage	168	272	45		30		30		25		25		25		25		20	
	178	283	348		378		398		413		423		433		443		453	

Site Prep

CH- D	10	10
Site Prep		l l
	SiteT	raller

Date Calculations

		2012	Ī															
Friday	30-Dec	6-Jan	13-Jan	20-Jan	27-Jan	3-Feb	10-Feb	17-Feb	24-Feb	2-Mar	9-Mar	16-Mar	23-Mar	30-Mar	6-Арг	13-Apr	20-Арг	27-Арг
Day No.	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Stat Day	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1	0	0	0
Lost Day	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
<u> </u>	Start																	
Friday	4-May	11-May	18-May	25-May	1-Jun	8-Jun	15-Jun	22-Jun	29-Jun	6-Jul	13-Jul	20-Jul	27-Jul	3-Aug	10-Aug	17-Aug	24-Aug	31-Aug
Day No.	1	6	11	15	20	24	29	33	38	42	46	51	55	60	63	68	72	77
Stat Day	0	0	0	1	0	0	0	0	0	1	1	0	0	0	1	0	0	0
Lost Day	1	0	0	0	0	1	0	1	0	0		0	1	0	1	0	1	0
Friday	7-Sep	14-Sep	21-Sep	28-Sep	5-Oct	12-Oct	19-Oct	26-Oct	2-Nov	9-Nov	16-Nov	23-Nov	30-Nov	7-Dec	14-Dec	21-Dec	28-Dec	2013 4-Jan
Day No.	81	85	90	94	99	102	107	111	116	121	125	130	134	139	143	147	146	149
Stat Day	1	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	5	2
Lost Day	0	1	0	1	0	1	0	1	0	0	1	0	1	0	1	1	1	0
Friday	11-Jan	18-Jan	25-Jan	1-Feb	8-Feb	15-Feb	22-Feb	1-Mar	8-Mar	15-Mar	22-Mar	29-Mar	5-Apr	12-Apr	19-Apr	26-Apr	3-May	10-May
Day No.	153	157	162	167	172	177	181	186	191	196	201	205	210	215	219	224	228	233
Stat Day Lost Day	<u>0</u> 1	0 1	0	0	0	0	0	0	0	0	0	0	0	0	0 1	0	<u>0</u> 1	0
LUX Day	<u> </u>		U	U	U	U	U	U	U	U	<u>, U</u>	U	U	U	<u> </u>	U	<u> </u>	U
Friday	17-May	24-May	31-May	7-Jun	14-Jun	21-Jun	28-Jun	5-Jul	12-Jul	19-Jul	26-Jul	2-Aug	9-Aug	16-Aug	23-Aug	30-Aug	6-Sep	13-Sep
Day No.	237	241	246	251	256	261	266	269	274	278	283	287	291	295	300	305	309	313
Stat Day	0	1	0	0	0	0	0	1	0	0	0	0	1	0	0	0	1	0
Lost Day	1	0	0	0	0	0	0	1	0	1	0	1	0	1	0	0	0	1
				1						1			1			2014		
Friday	20-Sep	27-Sep	4-Oct	11-Oct	18-Oct	25-Oct	1-Nov	8-Nov	15-Nov	22-Nov	29-Nov	6-Dec	13-Dec	20-Dec	27-Dec	3-Jan	10-Jan	17-Jan
Day No. Stat Day	318 0	322 0	327 0	331	335	339 0	344	348 0	353 0	357 0	362 0	366 0	371 0	375 0	376 4	378 3	382 0	387 0
Lost Day	0	1	0	1	0	1	0	1	0	1	0	1	0	1	0	0	<u>U</u>	0
Loa Day		•								<u> </u>		<u> </u>	·					
Friday	24-Jan	31-Jan	7-Feb	14-Feb	21-Feb	28-Feb	7-Mar	14-Mar	21-Mar	28-Mar	4-Apr	11-Арг	18-Apr	25-Арг	2-May	9-May	16-May	23-May
Day No.	391	396	400	405	408	413	417	422	426	431	435	440	443	448	452	457	461	465
Stat Day	0	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	0	1
Lost Day	1	0	1	0	1	0	1	0	11	0	1	0	1	0	1	0	1	0
Friday	30-May	6-Jun	13-Jun	20-Jun	27-Jun	4-Jul	11-Jul	18-Jul	25-Jul	1-Aug	8-Aug	15-Aug	22-Aug	29-Aug	5-Sep	12-Sep	19-Sep	26-Sep
Day No.	470	474	479	483	488	491	496	500	505	509	513	517	522	527	531	535	540	544
Stat Day	0	0	0	0	0	1	0	0	0	0	1	0	0	0	1	0	0	0
Lost Day	0	1	0	1	0	1	0	1	0	1	0	1	0	0	0	1	0	1
														2015				
Friday	3-Oct	10-Oct	17-Oct	24-Oct	31-Oct	7-Nov	14-Nov	21-Nov	28-Nov	5-Dec	12-Dec	19-Dec	26-Dec	2-Jan	9-Jan	16-Jan	23-Jan	30-Jan
Day No.	549	553	557	561	566	570	575	579	584	588	593	597	599	599	604	608	613	618
Stat Day	0	0	1	0	0	0	0	0	0	0	0	0	3	4	0	0	0	0
Lost Day	0	1	0	1	0	1	0	1	0	1	0	1	0	1	0	1	0	0
Friday	6-Feb	13-Feb	20-Feb	27-Feb	6-Маг	13-Mar	20-Mar	27-Mar	3-Арг	10-Apr	17-Арг	24-Арг	1-May	8-May	15-May	22-May	29-May	5-Jun
Day No.	622	626	630	635	640	645	650	655	659	664	669	674	679	684	689	693	698	703
Stat Day	0	0	1	0	0	0	0	0	1	0	0	0	0	0	0	1	0	0
Lost Day	1	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Criston			1st Move		1								l .c !				• • •	
Friday Day No.	12-Jun 708	19-Jun 713	26-Jun 718	3-Jul 722	10-Jul 727	17-Jul 732	24-Jul 737	31-Jul 742	7-Aug 746	14-Aug 751	21-Aug 756	28-Aug 761	4-Sep 766	11-Sep 770	18-Sep 775	25-Sep 780	2-0ct 785	9-0ct 790
Stat Day	0	0	0	122	0	0	0	0		0	0	0	0	1	0	0		0
Lost Day	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		· · · · · ·					Final Move	Ť				2016						
Friday	16-Oct	23-Oct	30-Oct	6-Nov	13-Nov	20-Nov	27-Nov	4-Dec	11-Dec	18-Dec	25-Dec	1-Jan	8-Jan	15-Jan	22-Jan	29-Jan	5-Feb	12-Feb
Day No.	794	799	804	809	814	819	824	829	833	838	841	841	846	851	856	861	866	871
Stat Day	1	0	0	0	0	0	0	0	1	0	2	5	0	0	0	0	0	0
Lost Day	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0



Fax: (416) 661-8923

Cornice Moulding

Instruction To Bidders RESIDENCES AT ARGENTO INC

Tender Closes

Wednesday, May 7, 2014 @ 3:00 p.m.

or EMAILED TO tmalliaros@tridel.com

Tom Malliaros, P.Q.S. Estimating Manager

Late Tenders will NOT be Accepted

Estimated Trade Start:

Feb-15



M3H 5S9 Office: (416)736-8353

Fax: (416) 661-8923

Cornice Moulding

Instruction To Bidders RESIDENCES AT ARGENTO INC

A.) Scope Of Work:	Included			
B.) Safety Scope Of Work:	Included			
<u>C.)</u>		<u>Drawings</u>	<u>Dated</u>	Specifications
<u>Architectural</u>	Rafael Bigauskas	ref.; Tender Drawing List	ref.; Tender Drawing List	Not Included
<u>Interior Design</u>	H & M	ref.; Tender Drawing List		Schedule E Finishes Specifications Manual
Suite Features and Finishes	Tridel		rgento - 18 Graydon rgento Townhomes-	
LEED VOC Limits		-	-	Schedule F
Construction Schedule		-	-	-
Project Director	Robert Tomei	(416) 736-2548	Direct Line	
Project Manager	Andres Valenzuela	(416) 736-2541	<u>Direct Line</u>	
Senior Estimator	Tom Malliaros	(416) 736-2526	Direct Line	
<u>Assistant Project</u> <u>Manager</u>	Andrea Willerding	(416) 645-7009	<u>Direct Line</u>	

4800 Dufferin Street Downsview, Ontario M3H 5S9

Telephone : (416) 661-9290 Fax : (416) 661-8923

PROJECT: ARGENTO Date: April 17, 2014

Location: Toronto

Prepared By: Rafeal Bigauskas

		<u> </u>	
DOCUMENT	DECCRIPTION	REVISION	DATE
NUMBER	DESCRIPTION	NUMBER	DATE
A4 O4	CONTEST DI ANI STATISTICS AND ODS MATRIX	40	14 Apr 14
A1-01 A1-02	CONTEXT PLAN STATISTICS AND OBC MATRIX	12	14-Apr-14
	FIRE RESISTANCE RATINGS PLANS		14-Apr-14
A1-03 A1-04	FIRE RESISTANCE RATINGS PLANS SITE PLAN	12	14-Apr-14
A2-01	P4 LEVEL CONTEXT PLAN UNDERGROUND PARKING GARAGE	12	14-Apr-14 14-Apr-14
A2-02	P4 LEVEL UNDERGROUND PARKING GARAGE	12	14-Apr-14
A2-02 A2-03	P3 LEVEL CONTEXT UNDERGROUND PARKING GARAGE	11	14-Apr-14
A2-04	P3 LEVEL UNDERGROUND PARKING GARAGE	12	14-Apr-14
A2-05	P2 LEVEL CONTEXT PLAN UNDERGROUND PARKING GARAGE	11	14-Apr-14
A2-06	P2 LEVEL UNDERGROUND PARKING GARAGE	12	14-Apr-14
A2-07	P1 LEVEL CONTEXT PLAN UNDERGROUND PARKING GARAGE	11	14-Apr-14
A2-08	P1 LEVEL UNDERGROUND PARKING GARAGE	14	14-Apr-14
A2-09	GARAGE PLAN DETAILS	11	14-Apr-14
A3-01A	GROUND FLOOR PLAN	14	14-Apr-14
A3-01B	GROUND FLOOR PLAN	11	14-Apr-14
A3-02A	2ND FLOOR PLAN	15	14-Apr-14
A3-02B	2ND FLOOR PLAN	13	14-Apr-14
A3-03A	3RD FLOOR PLAN	16	14-Apr-14
A3-03B	3RD FLOOR PLAN	15	14-Apr-14
A3-04	4TH TO 21ST FLOOR PLAN	17	14-Apr-14
A3-05	22ND FLOOR PLAN	16	14-Apr-14
A3-06	23RD - 27TH FLOOR PLAN	16	14-Apr-14
A3-07	28TH FLOOR PLAN	16	14-Apr-14
A3-08	MECH PENTHOUSE PLAN	14	14-Apr-14
A3-09	ELEVATOR MACHINE ROOM PLAN	13	14-Apr-14
A3-10	MECH PENT ROOF PLAN	12	14-Apr-14
A4-01	CONSTRUCTION NORTH ELEVATION	13	14-Apr-14
A4-02	CONSTRUCTION EAST ELEVATION	13	14-Apr-14
A4-03	CONSTRUCTION SOUTH ELEVATION	13	14-Apr-14
A4-04	CONSTRUCTION WEST ELEVATION	13	14-Apr-14
A4-05	PARTIAL SOUTH ELEVATION	11	14-Apr-14
A5-06	U/G GARAGE RAMP SECTIONS	12	14-Apr-14
A5-01	NORTH-SOUTH BUILDING X-SECTION	12	14-Apr-14
A5-02	EAST-WEST BUILDING X SECTION	12	14-Apr-14
A5-03	WALL SECTION	13	14-Apr-14
A5-04	WALL SECTION	13	14-Apr-14
A5-05	WALL SECTION	13	14-Apr-14
A5-07	WALL SECTION	13	14-Apr-14
A5-08	WALL SECTION	9	14-Apr-14
A6-01	STAIR A & B SECTIONS		14-Apr-14
A6-02	STAIR C & D SECTIONS		14-Apr-14
A7-01	MISC DETAILS		14-Apr-14
A7-02	MISCELLANOUS DETAILS	12	14-Apr-14
A7-03	WINDOW PETAL S	13	14-Apr-14
A7-04	WINDOW DETAILS	12	14-Apr-14
A7-05	DETAILS DIAN DETAILS	12	14-Apr-14
A7-06	PLAN DETAILS	14	14-Apr-14
A7-07	PLAN DETAILS	10	14-Apr-14
A7-08	SECTION DETAILS	8	14-Apr-14
A8-01	DOOR SCHEDULE		14-Apr-14
A8-02	ROOM FINISH SCHEDULE	11	14-Apr-14
A8-03	WALL CEILING & ROOF SCHEDULE		14-Apr-14
A8-04	WINDOW SCHEDULE GROUND FLOOR	13	14-Apr-14
A8-05	WINDOW SCHEDULE 2ND & 3RD FLOORS WINDOW SCHEDULE 4TH 6TH 6T OORS	13 14	14-Apr-14
A8-06 A8-07	WINDOW SCHEDULE 4TH-9TH FLOORS WINDOW SCHEDULE 10TH-21ST ELOORS	14	14-Apr-14
A8-07	WINDOW SCHEDULE 10TH-21ST FLOORS	14	14-Apr-14

4800 Dufferin Street Downsview, Ontario M3H 5S9

Telephone : (416) 661-9290 Fax : (416) 661-8923

PROJECT: ARGENTO Date: April 17, 2014

Location: Toronto

Prepared By: Rafeal Bigauskas

DOCUMENT NUMBER	DESCRIPTION	REVISION NUMBER	DATE
A8-08	WINDOW SCHEDULE 10TH-21ST FLOORS	14	14-Apr-14
A8-09	WINDOW SCHEDULE 22ND-27TH FLOORS	13	14-Apr-14
A8-10	WINDOW SCHEDULE 28TH FLOOR P/H ROOF	13	14-Apr-14
A8-11	WINDOW SCHEDULE MECH P/H ROOF	13	14-Apr-14
TH-A01	TOWNHOUSE TYPE A AND B GROUND FLOOR PLAN	12	14-Apr-14
TH-A02	TOWNHOUSE TYPE A AND B SECOND FLOOR PLAN	11	14-Apr-14
TH-A03	TOWNHOUSE TYPE A AND B THIRD FLOOR PLAN	12	14-Apr-14
TH-A04	TOWNHOUSE TYPE A AND B ROOF PLAN	11	14-Apr-14
TH-A05	TYPE A TOWNHOUSE ELEVATIONS	11	14-Apr-14
TH-A06	TYPE B TOWNHOUSE ELEVATIONS	11	14-Apr-14
TH-A07	TOWNHOUSE BUILDING SECTIONS	11	14-Apr-14
TH-A08	TOWNHOUSE WALL SECTIONS	12	14-Apr-14
TH-A09	DETAILS	12	14-Apr-14
TH-A10	DETAILS	6	14-Apr-14
TH-A20	TOWNHOUSE WALL CEILING ROOF DOOR SCHEDULE	12	14-Apr-14
THA-21	TOWNHOUSE WINDOW SCHEDULE	12	14-Apr-14

4800 Dufferin Street Downsview, Ontario M3H 5S9

Telephone : (416) 661-9290 Fax : (416) 661-8923

PROJECT: ARGENTO Date: April 17, 2014

Location: Toronto

Prepared By: Hefele Makowka

DOCUMENT	DESCRIPTION	REVISION	DATE
NUMBER	DESCRIPTION	NUMBER	<i>D/</i> (12
ID1.00	COVER SHEET	0	13-Mar-14
ID1.01	GROUND FLOOR REFERENCE PLAN (OVERALL)	0	13-Mar-14
ID2.01	PARKING LEVEL P1 CONSTRUCTION REFERENCE & FLOOR FINISHES	0	13-Mar-14
	PLANS (PARTIAL)		
ID2.02	PARKING LEVELS P2 - P4 CONSTRUCTION REFERENCE & FLOOR FINISHES PLANS (PARTIAL)	0	13-Mar-14
ID2.03	GROUND FLOOR CONSTRUCTION REFERENCE PLAN (PART 1)	0	13-Mar-14
ID2.04	GROUND FLOOR CONSTRUCTION REFERENCE PLAN (PART 2)	0	13-Mar-14
ID2.04A	GROUND FLOOR FLOOR FINISHES PLAN (PART 1)	0	13-Mar-14
ID2.04B	GROUND FLOOR FLOOR FINISHES PLAN (PART 2)	0	13-Mar-14
ID2.04c	GROUND FLOOR WINTER MATTING LAYOUT PLAN	0	26-Mar-14
ID2.05	2ND - 28TH FLOORS CONSTRUCTION REFERENCE & FLOOR FINISHES	0	13-Mar-14
ID2.03	PLAN		13-Wai-14
ID3.00	LIGHTING LEGEND	0	4-Apr-14
ID3.01	PARKING LEVEL P1 REFLECTED CEILING PLANS (PARTIAL)	0	13-Mar-14
ID3.02	PARKING LEVELS P2-P4 REFLECTED CEILING PLANS (PARTIAL)	0	13-Mar-14
ID3.03	GROUND FLOOR REFLECTED CEILING PLAN (PART 1)	0	13-Mar-14
ID3.04	GROUND FLOOR REFLECTED CEILIG PLAN (PART 2)	0	13-Mar-14
ID3.05	2ND - 28TH FLOORS REFLECTED CEILING PLANS	0	13-Mar-14
ID4.01	GROUND FLOOR FURNITURE & POWER & COMMUNICATIO PLAN (PART 1)	0	13-Mar-14
ID4.02	GROUND FLOOR FURNITURE & POWER & COMMUNICATIO PLAN (PART 2)	0	13-Mar-14
ID5.01	PLUMBING FIXTURE & WASHROOM ACCESSORY LAYOUTS	0	13-Mar-14
ID6.01	G-02 MAIN LOBBY LOUNGE ELEVATIONS	0	13-Mar-14
ID6.02	G-02 MAIN LOBBY LOUNGE ELEVATIONS & DETAILS	0	13-Mar-14
ID6.03	G-02 MAIN LOBBY LOUNGE DETAILS	0	13-Mar-14
ID6.04	G-02 MAIN LOBBY LOUNGE DETAILS	0	13-Mar-14
ID6.04A	G-01 VESTIBULE ELEVATIONS & ENTERPHONE DETAILS	0	13-Mar-14
ID6.05	G-04 CONCIERGE ELEVATIONS & DETAILS	0	13-Mar-14
ID6.06	G-12 MAIL PICK UP ELEVATIONS	0	13-Mar-14
ID6.07	G-51 GROUND FLOOR ELEVATOR LOBBY ELEVATIONS & DETAILS	0	13-Mar-14
ID6.08	P-02 P2-02 P1-02 PARKING LEVEL ELEVATOR LOBBY ELEVATIONS	0	13-Mar-14
ID6.09	G-15 THEATRE ELEVATIONS & DETAIL G-09 BOARDROOM DETAILS	0	13-Mar-14
ID6.10	G-16 DINING ROOM ELEVATIONS & DETAILS	0	13-Mar-14
ID6.11	G-25 PARTY ROOM ELEVATIONS & DETAILS	0	13-Mar-14
ID6.11A	G-25 PARTY ROOM ELEVATIONS & DETAILS	0	13-Mar-14
ID6.11B	G-25A PARTY ROOM BAR ELEVATIONS & DETAILS	0	13-Mar-14
ID6.12	G-23 EXERCISE ROOM & G-24 YOGA STUDIO ELEVATIONS	0	13-Mar-14
ID6.12A	G-23 EXERCISE ROOM & G-24 YOGA STUDIO ELEVATIONS & DETAILS	0	13-Mar-14
ID6.13	G-19 MENS WC G-21 WOMENS WC G-30 MENS CHANGEROOM & G-34 WOMENS CHANGEROOM ELEVATIONS & DETAILS	0	13-Mar-14
ID6.13A	G-31 MENS STEAM ROOM G-35 WOMENS STEAM ROOM & LOCKERS	0	13-Mar-14
ID6.14	ELEVATIONS & DETAILS ELEVATOR CABS ELEVATIONS & DETAILS	0	13-Mar-14
ID6.15	TYPICAL SUITE ENTRANCE	0	13-Mar-14
ID6.16	TYPICAL SUITE ELEVATOR LOBBY ELEVATIONS & DETAILS	0	13-Mar-14
ID6.16A	G-50 GUEST SUITE ELEVATIONS & DETAILS	0	13-Mar-14
ID6.17	TYPICAL SUITE CORRIDOR & ELEVATOR LOBBY CEILING SECTIONS	0	13-Mar-14
ID7.01	ROOM SCHEDULE	0	13-Mar-14
ID8.01	DOOR SCHEDULE	0	13-Mar-14
ID9.01	MOULDING SCHEDULE	0	13-Mar-14
		<u></u>	

Argento Townhomes

Features and Finishes SCHEDULE

Exterior General Finishes

- operable awning and casement windows* Architecturally designed thermally broken aluminum window frames with low-E coating, argon gas filled, double pane, sealed glazing units with
- Contemporary brick exterior finish.
- Architecturally designed and insulated front door with full frosted glass cut out and transom above
- Quality exterior grip set with dead bolt on main entrance door.
- 1.2 1.3 1.4 1.5 1.6 1.7 Colour coordinated metal flashing
 - Patio sliding door with full glass sidelight
 - Natural gas BBQ disconnect, water hose bib, electrical outlet and light in all rear ground floor patios
 - All 3rd floor rear decks shall receive an electrical outlet and light.
- approval). Front yard landscaping shall feature planters with combination of flowering shrubs, clipped hedges and ornamental trees (subject to site plan
- 1.10 Rear patio layouts feature lock stone pavers, shrub beds and privacy fencing (subject to site plan approval)
- 3rd floor rear decks shall feature a vinyl waterproof membrane system
- Automatic irrigation system for all planted areas

Interior General Finishes

- Reinforced concrete subfloors on Ground floor level and 5/8" tongue & groove plywood subfloors on upper levels
- Masonry demising wall between homes.
- 2.3 2.3 2.3 The ceiling height on the Ground floor level of the unit will be approximately 9', measured from the upper surface of the floor to the underside of the drywall ceiling, provided however that various areas of the dwelling unit may contain (or be subject to) ceiling bulkheads and/or dropped ceilings, in order to facilitate the installation of structural components, mechanical systems and/or ductwork, and accordingly in those areas of
- 2.4 components, mechanical systems and/or ductwork, and accordingly in those areas dropped ceilings the overall ceiling height will be reduced accordingly. approximately 8, measured from the upper surface of the floor to the underside of the drywall ceiling, provided however that various areas of the dwelling unit may contain (or be subject to) ceiling bulkheads and/or dropped ceilings, in order to facilitate the installation of structural the unit that are subject to said bulkheads and/or dropped ceilings the overall ceiling height will be reduced accordingly.

 The ceiling height on the 2nd floor level (featuring 2nd / 3nd bedrooms) and 3nd floor level (featuring master bedroom) of the unit will be The ceiling height on the 2nd floor level (featuring of the unit that are subject ರ
- 2.5 Smooth painted ceilings grace all Ground floor levels featuring the front entrance foyer, living room, dining room, kitchen and breakfast area
- 2.6 2.7 including all laundry room, mechanical room and all level bathrooms. White stippled ceiling finish to all other areas.

 Approximately 6" plaster cornice moulding in front entrance foyer, living room, dining room, kitchen and breakfast area*.

 Interior walls and smooth ceilings are primed and then painted with two coats of off-white, quality latex paint (bathroom(s) painted satin off white and all woodwork and trim painted with durable white semi-gloss paint). Paints have low levels of volatile organic compounds (VOCs).
- 6'-8" interior contemporary style doors with metal lever hardware to 8'-0" ceilings. 7'-0" interior contemporary style doors with metal lever hardware to 9'-0" ceilings.
- 2.8 2.9 2.10 have tile base. 5" paint finish, contemporary style baseboards with 3" matching door casing. Laundry, powder room, bathrooms and mechanical rooms to
- 2.11 2.12 Framed white panel board sliding doors to all bedroom closet(s) where applicable*
- Smooth white cultured marble window sills'
- Oak handrails, stringers and pickets stained to match ground floor plank engineered wood flooring***. installed only at tread Treads and risers are carpet. Underpad
- 2.14 at main entrance

ယ Floor Coverings

- 3.1 3.2
- ္သ Designer selected porcelain floor tiles*** in powder room and all bathrooms.

 Premium plank engineered wood flooring*** throughout the front foyer entrance, living room, dining room, kitchen and breakfast area*.

 Plush 50oz. green label nylon broadloom*** with underpad in all bedrooms, hallways, storage room*, linen closet*, walk-in-closet*, stair
- 3.4 landings* and staircases (underpad included only at stair tread). Ceramic floor tiles in the laundry and mechanical rooms***.

- Contemporary full height kitchen*** to underside of bulkhead, including full depth fridge upper cabinet with one bank of drawers. Cabinets
- come complete with metal hardware.

 Large kitchen island, for extra storage and eat-in; finished in choice of cabinetry*** and door*** with choice of granite or quartz countertop***.
- Choice of granite or quartz kitchen countertop*** with polished single square edge and undermount square double basin stainless steel sink
- Polished chrome single lever kitchen faucet.
- 4.2 4.3 4.4 4.5 4.6 4.7
- Energy Star high efficiency, time-delay stainless steel dishwasher.

 Energy Star high efficiency, stainless steel counter depth 18 cubic foot bottom mount refrigerator
- Built-in microwave with high capacity hood fan in stainless steel, vented to the exterior
- Self-cleaning 30 inch slide-in range with ceran top in stainless steel Choice of ceramic backsplash tile***.
- 4.8 4.9 4.10
- Energy saving fluorescent undercabinet lighting

Powder Room

- Single Bowl Wall Mount Corner Sink
- Beveled mirror above corner sink
- Porcelain tile flooring***
- Polished chrome single lever vanity faucet.
- Polished chrome bathroom accessories
- 5.3 5.3 5.5 5.6 5.7 Dual flush, low flow high performance toilet

9

- Contemporary cabinetry*** complete with metal hardware
- 6.1
- 6.3 6.4
- White cultured marble vanity top with rectangular shaped bowl. Integrated drawer(s)* in vanity millwork.

 Vanity-width shelf framed mirror, finish to match vanity, comple finish to match vanity, complete with centre pot light* and wall sconce

- 5' soaker tub* with polished chrome single lever faucet.
- 12" porcelain tile surround shall be provided to the 5' Porcelain tiles*** in tub* and shower enclosure*. Porcelain tile flooring*** soaker tub where both a soaker tub and shower exist*

- Shower light in ceiling of shower stalls*. Framed glass shower enclosure* with polished chrome single lever faucet.
- Pressure balanced and temperature controlled shower faucet
- High pressure, low-flow shower head
- 6.5 6.6 6.7 6.8 6.9 6.11 6.11 6.12
- Polished chrome single lever vanity faucet. Polished chrome bathroom accessories.
- 6.15 Dual flush, low flow high performance toilet.

- 7.1 7.2 7.3
- Heavy-duty wiring and receptacle for dryer.
 Ventilation to exterior with automatic relay sensor exhaust control.
 Stacked white front loading dryer and Energy Star high efficiency front loading washer (complete with stainless steel flexible hose water

Safety and Security

- ~ ∞ **∞** areas. Concierge service may be monitored remotely at times. Concierge, monitored community access systems including two-way communication from selected zones in underground garage and entry

- 8.2 8.3 4.8 Personally encoded intrusion alarm system, suite door contact and keypad connected to Concierge station.

 Contacts on all operable windows and doors at grade. Motion detectors only where applicable.

 Electronic communication system located in lobby vestibule permits guests to communicate with residents of the unit from the building entrance. Guests in the lobby can be viewed on the resident's television.
- 8.5 Surveillance cameras in selected locations in the building, grounds and garage may be monitored by the concierge. Emergency response key chain pendants, usable in selected areas within the underground garage, will alert the concierge of a distress call (2 pendants per unit).
- 8.7 Hardwired smoke detectors (s) and carbon monoxide detector(s)

Comfort System

- 9.1 9.2 9.3 9.4 9.5 High velocity air distribution system with temperature control for better indoor air quality Individual Energy recovery ventilator providing fresh air and heat recovery.
- Individually metering of electricity, hot water, heating and cooling consumption Adjustable supply air vents for indoor air control. Central building water filtration system.

Electrical Service and Fixtures

- 10.1 10.1 10.2 Individual service panel with circuit breakers
- Designer series receptacles and switches throughout.
- 10.3 Light fixture in front foyer entrance, breakfast area*, staircase landings*, hallway(s), walk-in closet(s)*, bedrooms, bathrooms and mechanical room and storage rooms*
- Capped ceiling light outlet in dining room.
 100 amperes electrical service.
- 10.4 10.5
- 10.6 Heavy-duty wiring and receptacle for stove.
- 10.7 floor level decks
- Weather proof electrical receptacles provided at front exterior entrances, rear patios and 3rd Light fixtures provided at front exterior entrances, rear patios and 3rd floor level decks. Lighting fixtures designed to fit long-lasting, energy saving lamps.
- 10.9 10.8
- 10.10 Potlights featured in the kitchen.

Communications

- 11.1
- Network Centre (high-speed wiring connection point) Advanced, star design in-home structured wiring. Ea Each telephone, cable or multi-port outlet within the home connects directly to the Network
- Pre-wired cable outlet in living room and bedroom(s).
- 11.3 11.4 Pre-wired telephone outlet in living room and bedroom(s).
- 11.5 determined by Vendor, One multi-port outlet (telephone and cable connections located on the same faceplate), will replace a prewired cable outlet ⊒. മ location
- 11.6 11.7 Category 5 telephone wiring to all telephone outlets ar RG-6 coaxial cable to all cable outlets and multi-ports. wiring to all telephone outlets and multi-ports

denotes availability determined by suite design to be confirmed at D&D
**** - denotes finishes to be selected from the vendor's samples. and finishes subject to change without notice, e vendor's sample, E. & O.E. Fel



Appendix A: VOC Limits for Adhesives, Sealants, Paints and Coatings

EQc4.1 - Adhesives and Sealants							
D 1 17	Max. VOC						
Product Type	content (g/L)						
Adhesives and Adhesive Primers							
Architectural Applications	ī						
Indoor Carpet Adhesives**	50						
Carpet Pad Adhesive **	50						
Wood Flooring Adhesive **	100						
Rubber Floor Adhesive **	60						
Subfloor Adhesive **	50						
Ceramic Tile Adhesives**	65						
VCT & Asphalt Tile Adhesive **	50						
Drywall & Panel Adhesives	50						
Cove Base Adhesives	50						
Multipurpose Construction Adhesives	70						
Structural Glazing Adhesive	100						
Substrate Specific Applications							
Metal to Metal	30						
Plastic Foams	50						
Porous Material (except wood)	50						
Wood	30						
Fiberglass	80						
<u>Sealant Primer</u>							
Architectural – Nonporous	250						
Architectural – Porous	775						
Other	750						
Specialty Applications							
PVC Welding	510						
CPVC Welding	490						
ABS Welding	325						
Plastic Cement Welding	250						
Adhesive Primer for Plastic	550						
Contact Adhesive	80						
Special Purpose Contact Adhesive	250						
Structural Wood Member Adhesive	140						
Sheet Applied Rubber Lining Operations	850						
Top & Trim Adhesive	250						
<u>Sealants</u>							
Architectural Sealant	250						
Non-membrane Roof Sealant	300						
Roadway Sealant	250						
Single-Ply Roof Membrane Sealant	450						
Other Sealant	420						
General Purpose Mist Spray - (%)	65						
General Purpose Web Spray -(%)	55						
Special Purpose Aerosol adh. (all types) - (%)	70						

EQc4.2 - Paints and Coatings		
	Max. VOC	
Product Type	content (g/L)	
Paints and Primers		
Interior Flat Paints *	50	
Interior Non-Flat Paints * or Interior Primer ***	150	
Anti-Corrosive/ Anti-Rust Paint	250	
Other Architectural Coatings		
Clear Wood Finishes: Lacquer**	550	
Clear Wood Finishes: Sanding sealers**	350	
Clear Wood Finishes: Varnish**		
Clear Brushing Lacquer	680	
Concrete-Curing Compounds**	350	
Dry-fog coating	400	
Fire-Proofing Exterior Coating	350	
Floor Coatings**	100	
Graphic Arts (sign) Coating	500	
Industrial Maintenance Coatings	250	
High Temperature IM Coatings	420	
Zinc-Rich IM Primers	340	
Japan/Faux Finishing Coating	350	
Magnesite Cement Coating	450	
Mastic Coating	300	
Metallic Pigmented Coating	500	
Multi-Colour Coating	250	
Pigmented Lacquer 5		
Pre-Treatment Wash Primer	420	
Sealers and Undercoaters**	200	
Quick-Dry Enamel	250	
Quick-Dry Primers, Sealers, Undercoats	200	
Recycled Coatings	250	
Roof Coating	250	
Roof Coatings, Aluminum	500	
Roof Primers, Bituminous	350	
Rust Preventative Coatings	400	
Shellac: Clear	730	
Shellac: Pigmented	550	
Specialty Primers	350	
Stains, Interior**	250	
Swimming Pool Coating – Repair	340	
Swimming Pool Coating – Other	340	
Waterproofing Sealers**	250	
Waterproofing Concrete/Masonry Sealers**	400	
Wood Preservatives	350	
Low-Solids Coatings	120	

Notes
Materials/products that are within the building's
weatherproofing layer must comply with the given VOC limits.
* A coating is considered flat if it has a gloss of less than 5 on a 60-degree meter, or less than 15 on an 85-degree meter. If the gloss

EQC4.3 - Flooring agnesives and finishes	
Product Type	Max. VOC content (g/L)
Grout	250
** Other relevant products, noted above, as they apply to flooring	see above



SCHEDULE "C"

Safety Scope of Work: herein referred to as the "Contractor"

This Schedule applies to the Contractor, its employees, any sub-contractors hired by the Contractor and any other agent acting on behalf of the Contractor.

REGULATORY COMPLIANCE

- The Contractor acknowledges the importance and application of the Occupational Health and Safety Act, R.S.O. 1990, Chapter O.1 as amended, hereafter referred to as "The Act", and agrees that all work conducted by or services performed by the Contractor ("Work") will be in full compliance with The Act.
 - Furthermore, the Contractor agrees to abide by all applicable Regulations, in connection with The Act, including, but not limited to the Regulations for; Construction Projects, Window Cleaning, Designated Substances, Workplace Hazardous Materials Information System and Confined Spaces.

PROJECT SPECIFIC SAFETY PERFORMANCE REQUIREMENTS

The following are Specific Safety Performance Requirements to ensure and enhance site safety - they do not replace or diminish The Act and its Regulations.

Supervision

- The Contractor agrees to have a "competent person" (e.g. a foreman) act as a supervisor whenever its workers are on site. The supervisor will carry out the requirements and obligations of The Act including those of a "Supervisor" as defined by The Act.
- The Contractor's workers are not permitted to work unsupervised.
- The name of and contact information for the supervisor must be provided to the Owner prior to commencing work.

Documentation

In addition to the supervisor information, prior to arrival and commencement of Work, the Contractor will provide a copy of the following documentation to the Owner at its office;

- Registration of Employers Engaged in Construction, Form 1000 (Ministry of Labour)
- 2. The Contractor's Safety Policy and Safe Work Procedures
- 3. WHMIS Material Safety Data Sheets for all controlled substances to be used by the Contractor
- A current and valid "clearance certificate" issued by the Workplace Safety and Insurance Board (WSIB)

Training

In

- The Contractor agrees to ensure that every person at the site for the Contractor's benefit and by the Contractor's invitation is trained in:
 - All of the actual and potential hazards associated with both their Work and the job site.
 - 2. Fall Protection
 - 3. WHMIS
 - Any trade and Work specific training required by The Act and Regulations.
- Trades Qualification and Apprenticeship Act ('TQAA'). For trades governed by the TQAA, the Contractor agrees to ensure that only licensed workers (journeymen and apprentices) report to the Siste to perform Work on behalf of the Contractor.

 The Contractor agrees to ensure that copies of all the above training certificates and licenses are made available to the Owner on request.

Personal Protective Equipment

- The Contractor acknowledges and agrees to ensure that all workers arriving at the site arrive with and wear the prescribed personal protective equipment ('PPE'). (CSA approved hard hat and safety boots)
- Furthermore, the Contractor agrees to ensure that PPE which is not required at all times is immediately available to all of the Contractor's workers who may need it. (e.g. fall protection, safety glasses, dust masks, face shields, hearing protection, gloves, etc.)
- The Contractor agrees to ensure that adequate training is provided to their workers for all PPE which is required to be used or worn.

Housekeeping

The Contractor shall ensure that ongoing housekeeping is performed by its workers to prevent hazardous conditions from occurring. Good and effective housekeeping shall be performed by the Contractor, relating to all material and garbage belonging to the Contractor, on a daily basis.

Material and garbage shall not be allowed to block access/egress routes, impede access to emergency equipment or present a fire hazard. The Owner reserves the right to perform cleanup on behalf of the Contractor if any of the above conditions occur, and hold the Contractor responsible for all costs relating to the cleanup.

Incident Reporting

The Contractor must immediately report all injuries, incidents and serious near-misses to the Owner in writing while working on the Owner's site. The Contractor shall, in writing, inform all of its workers of the requirement to immediately inform the Contractor's supervisor, who will then inform the site supervisor of the occurrence. Incidents which require notification of external authorities (e.g. Ministry of Labour) must be coordinated through the Owner.

Safety Talks

The Contractor understands that it is a requirement of this contract to conduct a weekly safety talk. The talk should include a relevant safety topic and be discussed with all of the Contractor's workers working at the site that day. The facilitator and workers should sign an acknowledgement of the safety talk and a copy is to be provided to the site office at the end of each week.

Workplace Safety Inspections

The Contractor understands that it is a requirement of this contract to conduct a weekly workplace safety inspection. The inspection should include all tools and equipment being used by the Contractor's workers as well as the general area(s) in which the workers are working. The Contractor should sign an acknowledgement of the safety inspection and a copy is to be provided to the site office at the end of each week.

Enforcement of Safety Requirements

The Contractor acknowledges that the enforcement of The Act, Regulations and the Owners requirements is the primary responsibility of the Contractor and its supervisor(s). The Contractor will ensure that as part of

24: 1 . 11 41 C	W' (11 (1 ()
itialed by the Contractor's Representative	Witnessed by the Owner's Representative

the supervisor's core duties, ensuring the safety of the Contractors workers and enforcement of all aspects of the safety program is included.

In addition, the Owner will monitor safety and enforce safety performance and reserves the right to remove permanently, from the site, any worker (including the supervisor) who violates any aspect of the safety program. Furthermore, the Contractor understands and agrees that it is the Contractor's sole responsibility to maintain the contracted Work schedule despite the removal of any worker or workers due to safety violations. Additional costs incurred to maintain production schedules are the sole responsibility of the Contractor under the circumstances outlined above.

Failure to Perform

If a safety concern is brought to the Contractor's attention and the Contractor fails to resolve the concern in a reasonable manner and time frame satisfactory to the Owner, at its sole discretion the Owner may take such corrective action as it sees fit. The Contractor shall reimburse the Owner for all of the costs, expenses and legal fees incurred in correcting all safety concerns the Contractor has been notified of and that the Contractor has failed to correct to the Owner's full satisfaction, and all such costs, expenses and legal fees may be set-off against any monies owing to the Contractor, and the Contractor hereby agrees and authorizes the Owner so to do.