

# 233-S PCF Demolition Project

RadCon practices and techniques

Stephen L. Bump, CHP

Daniel S. Mantooth, CHP

William J. Knight, HP

233-S Plutonium Concentration Facility  
D&D Project

# The 233-S Facility



- Located North of the 202-S “Redox” Facility.
- The process area was a reinforced concrete structure 37 feet high, 86 feet long and 43 feet wide with twelve-inch walls and six-inch thick floors.
- The non-process areas were a single story structure with eight-inch walls and six-inch thick floors.

# Existing Conditions

- In 1956 a spill of approximately 32 grams of plutonium solution caused extensive contamination of the facility, including outside areas.
- In 1963 a fire spread gross alpha contamination to all areas of the facility, including the outside roof area.
- Major Decon activities occurred from 1978 to 1981. Stabilization of the facility was completed in 1987.
- Dismantlement and removal of process equipment began in 1996. Contamination levels range from 2,000 d/m/100 cm<sup>2</sup> to greater than 20,000,000 d/m/100 cm<sup>2</sup>.



# D&D Radiological Control - The Challenge

- Different Than Nuclear Operations
  - Contamination control and monitoring is much more difficult when demolishing facilities
    - Removing walls creates a lack of containment
    - Weather conditions affect the ability to monitor contamination (e.g., detecting alpha contamination in the rain)
    - Temporary facilities and dressing rooms are used



# D&D Radiological Control – The Solution

- Apply Innovative Techniques To Maintain Radiological Control While Still Meeting Requirements



# Innovation With 233-S Demolition Contamination Control

## Grout/Section/Remove

- Requires massive equipment
- Impractical for location
- Unacceptable cost/schedule

## Shear Only

- Cont. Area >300 M (386 ft.)
- Least cost

## Shear w/Containment Tent

- Expensive
- Personnel risks
- Did not demonstrate open air

## Shear w/Controlled Demolition

- Cont. Area manageable 40 M (131 ft.)
- Existing equipment available
- Acceptable cost/schedule



# Radiological Planning



- Extensive interfacing with D&D Operations, Waste Management, and demolition vendors is needed in order to establish an effective contamination control program while allowing efficient personnel and vehicle access.
- Planning and execution of an effective decontamination program is a vital part of the process.

# Radiological Planning

- Establishment of routine sample points at the CA/RBA boundary allows the detection of low level contamination in time to effect remediation efforts without impacting demolition activities.






# Radiological Planning

Continuous monitoring of Airborne contamination levels is a necessity.



- Four Canberra “Alpha Sentry” Continuous Air Monitors provided real time remote monitoring.
- A portable Eberline Alpha-5 monitor provided spot monitoring.

# Radiological Planning



- Atmospheric dispersion modeling can provide a pre-demolition estimate of releases of radioactive material and assist in site boundary planning.
- No indication of spread beyond boundary

# Administrative Controls

- A control point desk at the demolition area access point allows on the spot decisions to expedite job flow.



# Administrative Controls

- All personnel were issued radios to allow rapid and effective communication.



# Administrative Controls

- Keeping non-essential personnel outside of the work area prevents over tasking both radiological and operational resources.





# Engineering Controls



- Whenever active demolition was paused, the application of fixatives to the demolition site mitigated the windborne spread of radioactive material.



# Engineering Controls



- Misting Nozzles were installed on the Shear and bucket to mitigate the spread of airborne contamination at the source.



# Engineering Controls



- Fog Canons provide an effective way to further limit the spread of airborne contamination during active demolition.



# Engineering Controls



- In order to expedite the release of transport vehicles, a clean pathway to the ERDF Box was created using disposable plastic sheeting.

# Engineering Controls

- The application of plastic wrap allowed highly contaminated areas of contamination exposed during cutting to be rapidly fixed prior to packaging.



# Mockups – A vital tool.



- Utilizing Mockups and walk downs allowed workers to solve problems and refine procedures in a safe environment, saving time and exposure in the demolition zone.



# Mockups – A vital tool.



- Utilizing Mockups and walk downs allowed workers to solve problems and refine procedures in a safe environment, saving time and exposure in the demolition zone.



# Mockups – A vital tool.



- Utilizing Mockups and walk downs allowed workers to solve problems and refine procedures in a safe environment, saving time and exposure in the demolition zone.

# Mockups – A vital tool.



- Utilizing Mockups and walk downs allowed workers to solve problems and refine procedures in a safe environment, saving time and exposure in the demolition zone.

# Problems and Solutions

## Excessive Wind Speeds



- Wind speeds in excess of 65 mph were recorded at the demolition site. Although the application of fixatives prevented the spread of contamination, equipment tents did not fair so well.
- “Hardening” of the tents to survive higher winds speeds was necessary.

# Problems and Solutions

## Temperature Extremes



- Temperatures, both Hot and Cold, became a limiting factor for work activities.

# Problems and Solutions

High Temperatures reached 112°



- A work/rest regimen based on WBGT index was used.
- Evaporative coolers were located in worker cool down areas.





# Problems and Solutions

Low Temperatures reached -14°



- Cold weather gear was issued to all outside workers.
- Modifications were made to existing RWPs to allow workers to wear cold weather gear under their protective clothing.
- A heated staging area was built to allow workers to remain warm without leaving the area.



# Problems and Solutions

## Change Trailer Size



- The size of the change trailer was inadequate for the number of personnel entering and exiting the area.
- The level of PPE required for entry into the demolition area required the presence of additional personnel to assist workers.
- A new trailer was procured and configured based on feedback from the workers in the field.

# Expect The Unexpected



**Contaminated Paint  
Flaking Off Pipes**



**Pipe With Legacy Nitric  
Acid...Found When Cut**

# Beginning to End



- Demolition commenced October 22<sup>nd</sup>, 2003.



- Slab on Grade was achieved April 30<sup>th</sup>, 2004

# The Final Steps.



- June 3<sup>rd</sup>, 2004 - A worker levels the clean gravel fill in preparation for pouring the final grout cap.
- June 8<sup>th</sup>, 2004 - The final concrete cap is poured.



# Lessons Learned

- D&D Experience May Be Hard To Find
- Use All Available Resources
  - DOE Complex
  - Vendors
  - ALARA Center
  - HAMMER
- ALARA Is An Ongoing Process
- Don't Underestimate The Impact Of Environmental Condition
- Have The Right Equipment At The Beginning
- Tailor Radiological Monitoring To The Project
- Look For Innovative Contamination Control Techniques



# Summary

- Plan Carefully
- No Two Projects Are The Same
- Listen To Co-Workers
- Use Responsible Innovation
- Keep An Open Mind and...Always Expect The Unexpected



# The End



WHAT ONCE WAS, IS NO MORE



233S DEMOLITION 2005

