



#### Pipeline Unplugging Technology Demonstration

#### Dwayne McDaniel, Amer Awwad, Jose Varona, Rajiv Srivastava, David Roelant

Savannah River/Hanford/Idaho Technical Exchange

October 10, 2007

# **Technology Need**

- At least one cross-site transfers line in Hanford is plugged. Several other pipelines maybe partially plugged.
- Pipeline plugging can and will happen during cross-site slurry pipeline transfers
  - Plugged pipelines are difficult to repair and put back into operation. Usually abandoned and new ones are constructed
    - Schedule delays
    - Increased costs
- Unplugging technologies are needed to remove the blockages in transfer lines

# History/Approach

- Demonstrations carried out during FY02 to screen pipeline unplugging technologies for applicability at DOE sites
  - Roto-router, Aqua-Miser, Hydrokinetics, AEAT
- FY07-FY08 Technology Demonstrations
  - NuVision (formerly AEAT)
    - fluidic wave-action methodology
  - AIMM's Hydrokinetics
    - combination of pressure pulse/sonication

# Objective

- Assist DOE with pipeline unplugging technology evaluation and qualification
  - Provide understanding of the underlying physics
    - Propagation of pressure pulse
    - Pressure amplification factor
    - Effects of bends and expansion joint
- Determine whether the technology can unplug a pipe at 19,000 ft from the inlet

## **Test-beds**

- The testing parameter (unplugging time, unplugging effectiveness etc.) obtained at three different lengths will be used to predict the corresponding value for a maximum distance to blockage of 19,000 ft.
- Done by fitting a curve on the test data and extrapolating to 19,000 ft.
- Since most of the rheological data is non-linear, L1, L2 and L3 can be selected according to the geometric progression, L = ar<sup>N</sup>, where N = 1,2,3...Selecting a = 100 ft and r = 1.3, gives for N = 4, L1 = 286 ft, N = 7, L2 = 627 ft, N = 11, L3 = 1792 ft and N = 20, L4 = 19005 ft.



L=ar <sup>N</sup>							
<b>a</b> 100	<b>r</b> 1.3	<b>N</b> 3	L 220				
100	1.3	4	286				
100	1.3	5	371				
100	1.3	6	483				
100	1.3	7	627				
100	1.3	8	816				
100	1.3	9	1060				
100	1.3	10	1379				
100	10	44	1702				
100	1.3	11	1792				
100	1.3	12	2330				
100 100 100	1.3 1.3 1.3	11 12 13	2330 3029				
100 100 100 100	1.3 1.3 1.3 1.3	11 12 13 14	2330 3029 3937				
100 100 100 100	1.3 1.3 1.3 1.3 1.3	11 12 13 14 15	2330 3029 3937 5119				
100 100 100 100 100 100	1.3 1.3 1.3 1.3 1.3 1.3	11 12 13 14 15 16	2330 3029 3937 5119 6654				
100 100 100 100 100 100	1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3	11 12 13 14 15 16 17	2330 3029 3937 5119 6654 8650				
100 100 100 100 100 100 100	1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3	11 12 13 14 15 16 17 18	2330 3029 3937 5119 6654 8650 11246				
100 100 100 100 100 100 100 100	1.3 1.3 1.3 1.3 1.3 1.3 1.3 1.3 1.3	12 13 14 15 16 17 18 19	2330 3029 3937 5119 6654 8650 11246 14619				
100 100 100 100 100 100 100 100 100	1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3   1.3	11 12 13 14 15 16 17 18 19 20	2330 3029 3937 5119 6654 8650 11246 14619 19005				

Figure 1. (a) Using equal distance between the section lengths can give an under-prediction of the real behavior of the slurry data.

(b) Using geometric progression for the section lengths will help to predict the data for 1900ft more accurately.

#### Test-bed #1 (285 ft)



#### **Test-bed #2 (621 ft)**





# Test-bed (during fabrication)



#### Test-bed #3: 1797 ft





# Instrumentation



NuVision and FIU transducers after an elbow

NuVision and FIU transducers at the clear section

## **Test-bed Clear Section**



Ball valve

Blockage section

#### Nu-Vision's Fluidic Wave Action Technology



## **Nu-Vision Equipment**



# NuVision Equipment (cont)



Control Jet pump Vacuum Control valves

### Kaolin clay plug







	Mean Particle Diameter µm	Shear Strength kPa	Density g/cm3
Kaolin water mixture (66 wt% kaolin in water)	1.02	3.5	1.65
Tank Sludge	1.2	0 to 5	1 to 2

# Aluminum gel plug

#### (Media files deleted)

- Matrix Solution:
  - 450 ml of distilled water
  - 375 g of Al(NO3)3.9H2O
- Gelling solution:
  - 350 ml of distilled water
  - 120 g of NaOH
  - 53 g of Na2CO3
- Solutions are prepared in separate beakers and the gelling solution is mixed into the matrix solution rapidly.
- 800-850 ml of Al-gel is obtained.



# Phosphate gel plug

Component	Molarity
NaAlO <sub>2</sub>	1
NaOH	2
Na <sub>2</sub> CO <sub>3</sub>	0.1
NaNO <sub>3</sub>	7
Na <sub>3</sub> PO <sub>4</sub> 12H <sub>2</sub> O	0.3

- Constituents are mixed in water at 55 - 60°C
- Final solution is cooled down to room temperature rapidly
- Batches of phosphate are kept in fume hood to dry and then placed in the 3" pipe
- More gel is added as the water drains while in the pipe





# Project Gantt

ID	0	Task Name	Duration	Start	Finish	ruar March 1 April 1 May 1 June 1 July 1 August 1 Septemb October 1 Novembe Dec 2/11/2/25/3/11/3/25 4/8 4/22/5/6 5/20 6/3 6/17 7/1 7/15 7/29/8/12/8/26 9/9 9/23/10/7 0/2 11/4 1/1 12/2
1		Pre-testing Phase	60 days?	Tue 6/12/07	Mon 9/3/07	
2	<b>III</b>	Final Design of Test Bed	2 days	Tue 6/12/07	Wed 6/13/07	
3	$\checkmark$	Space Committee Approval	14 days	Thu 6/14/07	Tue 7/3/07	
4	$\checkmark$	Procurement of Test bed Equipments	57 days	Thu 6/14/07	Fri 8/31/07	
5	$\checkmark$	Setup the simulant mixer	15 days	Thu 6/14/07	Wed 7/4/07	
6	=	Preparing the simulants	29 days	Thu 6/14/07	Tue 7/24/07	
7	$\checkmark$	Safety review	1 day	Wed 7/11/07	Wed 7/1 1/07	
8	$\checkmark$	Safety mitigation	18 days?	Thu 7/12/07	Mon 8/6/07	
9	$\checkmark$	Setup the test bed for case #1	22 days	Thu 7/12/07	Wed 8/22/07	
10	$\checkmark$	Pressure testing and calibration	3 days	Wed 8/29/07	Fri 8/31/07	
11	$\checkmark$	Nuvision ships the complete unit to FIU	7 days	Fri 8/24/07	Mon 9/3/07	
12		Testing Phase	60 days	Tue 9/4/07	Mon 11/26/07	
13		Unblocking Trials	40 days	Tue 9/4/07	Mon 10/29/07	<b></b>
14	<b>.</b>	NuVision Setup/Commisioning	3 days	Tue 9/4/07	Thu 9/6/07	Let a state of the
15	<b>√</b> <sup>∉</sup>	Unplugging tests case #1: 285ft	17 days	Fri 9/7/07	Mon 10/1/07	· · · · · · · · · · · · · · · · · · ·
16	$\checkmark$	NuVision establishes equipment parameters	7 days	Fri 9/7/07	Mon 9/17/07	
17	$\checkmark$	Perform unblocking tests per FIU matrix	9 days	Tue 9/18/07	Fri 9/28/07	
18	$\checkmark$	Setup test bed for case #2	1 day	Mon 10/1/07	Mon 10/1/07	
19		Unplugging tests case #2: 621ft	12 days	Tue 10/2/07	Wed 10/17/07	
20		NuVision establishes equipment parameters	4 days	Tue 10/2/07	Fri 10/5/07	
21		Perform unblocking tests per FIU matrix	7 days	Mon 10/8/07	Tue 10/16/07	
22		Setup test bed for case #3	1 day	Wed 10/17/07	Wed 10/17/07	
23		Unplugging tests case #3: 1797ft	8 days	Thu 10/18/07	Mon 10/29/07	
24		Nu Vision establishes equipment parameters	3 days	Thu 10/18/07	Mon 10/22/07	
25		Perform unblocking tests per FIU matrix	5 days	Tue 10/23/07	Mon 10/29/07	
26		Project Reporting	20 days	Tue 10/30/07	Mon 11/26/07	
27		Draft Final Test Report	5 days	Tue 10/30/07	Mon 11/5/07	
28		Review and Comments	10 days	Tue 11/6/07	Mon 11/19/07	
29		Final Report	5 days	Tue 11/20/07	Mon 11/26/07	

## **Demonstration Status**

0

0

1

1

12

13

$\left( \right)$	Trial #	Reducer	Elbow at Outlet	Discharge Length	Blockage length	Expansion Joint	Blockage Type	Distance to Blockage
	1	0	1	21ft	4ft	1	Kaolin	285ft
	2	0	1	21ft	4ft	1	Phosphate	285ft
	3	0	1	21ft	4ft	1	Al-gel	285ft
Completed	4	1	1	21ft	4ft	1	Kaolin	285ft
$\prec$	5	0	, 1 ,	21ft	4ft	0	Kaolin	285ft
	Trial #	Reducer	Elbow at Outlet	Discharge Length	Blockage length	Expansion Joint	Blockage Type	Distance to Blockage
	6	0	1	21ft	4ft	1	Kaolin	621ft
	7	0	1	21ft	4ft	1	Phosphate	621ft
	8	0	1	21ft	4ft	1	Al-gel	621ft
Current –	9	0	, 1 ,	21ft	4ft	0	Kaolin	621ft
$\left[ \right]$	Trial #	Reducer	Elbow at Outlet	Discharge Length	Blockage length	Expansion Joint	Blockage Type	Distance to Blockage
	10	0	1	21ft	4ft	1	Clay	1797ft
Future	11	0	1	21ft	4ft	1	Phosphate	1797 ft

21ft

21ft

4ft

4ft

1

0

Al-gel

Kaolin

1797 ft

1797 ft

# **Demonstration Videos**



(Media files deleted)

#### **Data Acquisition**



**Control variables** 

Drive pressure Suction time Drive time Vent time Vacuum level



# Summary

- Completed testing on the 285 ft test-bed; Current testing on the 621 ft test-bed.
- Hanford TFO team engineers will be at FIU to observe the unplugging tests first-hand.
- NuVision's fluidic system benefits
  - short mobilization and demobilization times
  - remote operation; minimal intervention
  - can negotiate numerous elbows, etc.
  - relatively low drive pressures (3 to 4 bar)
  - can be used to deliver chemical solvent to the blockage
  - location of the blockage can be determined by the amount of water required to back-fill the pipeline

Detailed information resulting from the testing will provide the DOE end-user with sufficient data and understanding of the technology, and its limitations so that management decisions can be made whether the technology has a reasonable chance to successfully unplug a pipeline, such as a cross site transfer line or process transfer pipeline at the Waste Treatment Plant.

# Acknowledgments

- Gary Josephson, PNNL
- Dennis Hamilton, CH2M
- Rick Raymond, CH2M
- Blaine Barton, CH2M
- Erik Kezler & project team, NuVision
- Aruna Arakali, WTP
- FIU support staff and students
  - Geovanny, Renee, Ranga, Praneeth, Romani