



Figure 2-4
Mile 105 Oxbow Restoration

South of Percha Dam is a 6.6 ac former meander diked off during RGCP construction. This oxbow was originally the main channel of the river until the current channel was excavated. The oxbow is heavily vegetated.

Integrated USIBWC Land Management Alternative

Point Project Measures	ID	#	Area (ac)
Native Vegetation Planting/enhancement	105A	1	6.6

Targeted River Restoration Alternative

Point Project Measures	ID	#	Area (ac)
Open former meander	105C	1	6.6

