





CMS: Opportunities for Additional Support






LHC Schedule

- Last magnet installed March 2007
- Machine and experiments closed 31 August 2007
- First collisions November 2007
 - Engineering run at $\sqrt{s}=900$ GeV
 - Squeeze only toward end of run, $L\sim 10^{29}$ cm⁻²s⁻¹
 - 3 month shutdown over winter months
- 75ns commissioning down to 25ns April-October 2008
 - First collisions at $\sqrt{s}=14$ TeV
- Half intensity at 25ns 2009 physics run
 - Followed by longish shutdown






UXC55 Installation Schedule



Section	CMS Designation	Weight in tonnes
1	HF+	250
2	YE+3	410
3	YE+2	880
4	YE+1	1310
5	YB+2	1250
6	YB+1	1250
7	HB+	700
8	YB0	1920
9	HB-	700
10	YB-1	1250
11	YB-2	1250
12	YE-1	1310
13	YE-2	880
14	YE-3	410
15	HF-	250

“15 piece jigsaw puzzle”







CMS Underground Caverns

Tracking System connections:


- Fiber optics
- Low voltage cables
- Cooling pipes (C_6F_{14})
- gas



YB2 lowered on January 19



Tracker Services




Organized in PP1's in 53° crack.




Tracking System Readiness



TIB/TID+




TEC+



TOB inside thermal screen

All strip modules at Tracker Integration Facility since last year. Slice tests now underway. Will need to stop ~May in preparation for move to Point 5. Over 70 million channels in final Tracking system!



Two forward pixel half disks, recently delivered for the engineering run.



Tracker Integration Schedule

- YB0 lowered (February)
 - HCAL +/- installation 2 weeks
 - PP1 +/- installation 1 week
 - HCAL/ECAL pipework 3 weeks
 - Tracker pipework 8 weeks
 - Tracker cables 6 weeks
 - 11 cables/shift, 2 shifts/day, 4 crews/shift 5 days/week
 - ECAL cabling + Tracker fibers 8 weeks
 - 2 shifts/day, 2 crews/shift, 6 days/week
 - Infrastructure installation 5 weeks
- 33 weeks**

From December CMS Week Tracker meeting presentation
by S. Moccia. Many operations necessarily serial.



Tracker Integration Schedule cont.

- The installation of CMS Tracker services is clearly a critical path item.
- In addition to the actual installation of services there is a LOT of engineering and drafting work that needs to be done in support of this effort.
- Recent discussions involving CMS Management have led for an appeal for additional resources to help cope with the very tight schedule.

In the words of one anonymous wit: “It is clear that a SURGE is needed...”



On-going PPD Effort on Integration

■Stefano Moccia

- In residence at CERN
- Recently assigned to CMS Integration office; playing critical role in Tracker I&I effort.

■Linda Bagby

- Layout of Tracker services
- Stack 4 boards (PP1)
- At least 6 months effort in 2007


http://www-ppd.fnal.gov/EEDOffice-w/Projects/CMS/Silicon_TRacker/index.html

■Patch Panel 1 (PP1) boxes

- 2*16 stainless steel shallow boxes
- Marvin Johnson (ret., CERN) and Dick Loveless (WI)



■Pixel PP1 design, modeling, and installation

- Rauch, 4 months 50-60%
- Howell, small fraction





On-going PPD Effort on Integration



- **PP1 Boards**
 - 224, 9 connector boards
 - Green, Huffman
 - Will assemble locally in February and March
- **PP1 Control Stack 4 boards**
 - 3-connector boards similar to PP1 9-connector boards
 - 236 connector pairs for TOB/TEC
 - 120 pairs for TIB/TID
 - Bagby, Green, Huffman
 - Through April
- **PP1 load boxes**
 - 20 boxes to test installed LIC cables
 - Green, Huffman
 - Complete by March?
- **CAEN power supply filter addition**
 - Engineering (Johnson), Green, Huffman

http://www-ppd.fnal.gov/EEDOffice-w/Infrastructure_group/Huffman/Web/default.html



New Opportunities

- **PP1 freon piping layout**
 - Define 3D layout of pipes inside PP1
 - ~20 construction drawings
 - Some input needed by end of February; several months effort
 - Complicated pipe bends \Rightarrow imply pre-bending on CNC machines
 - Will require close contact with Marvin Johnson and Dan Wenman (WI PSL), Rauch?
- **Dry air system for the Tracking system**
 - Design and build a rack or panel that carries all the manifolding and instrumentation for pressure and flow regulation and safety devices.
 - Standalone project following initial visit to CERN
 - Del Allspach? UCSB engineers?
 - Needed by August
- **Control system to prevent condensation on the insulation surrounding the cooling pipes**
 - Heating wires will be identified and purchased in the next few weeks.
 - Engineering is needed for a system to control the heating: power supplies, interlocks, etc.
 - Needed by end of year.



New Opportunities

- **Cooling pipe routing on balconies**
 - Requires presence at CERN due to many interference issues
 - 2 months of designer time
 - Needed by mid-April
- **Detailer to work with Stefano**
 - 5 ton, 10m² platform for 6m working height
 - Tooling for Tracker pre-cabling work from PP1's to balcony racks.
 - Work could be done at FNAL with some travel to CERN
 - Platform drawing needed by mid-March
- **Supervisors for technician crews?**
 - Willingness to work long hours and linguistic abilities in either Bulgarian, Chinese, French, or Russian would be considered a plus.

Except for the last point the input was provided by Stefano Moccia.