

Progress in Acumentrics' Fuel Cell Program

August 7, 2007



Outline

> Overview >Cell Technology Process Developments Generator Developments ➤Coal Systems SECA Phase I Machine Performance > Summary



Acumentrics Corporation



~ 80 Employees
Manufacturing since 1994
Based in Westwood, Mass.
~40,000 sq. ft facility
Profitable for the past 24 months

Critical disciplines in-house

 Electrical Engineering
 Mechanical Engineering
 Chemical Engineering
 Thermal Modeling
 Ceramics Processing
 Manufacturing
 Sales & Marketing
 Automation

Finance



Acumentrics *Battery based UPS*







Industrial-UPS® Commercial

> **Rugged-UPS®** Military

Features:

- Sealed electronics
- Able to withstand vibration
- Unity power factor input
- Wide input 80VAC 265VAC
- Isolated 120 / 240VAC output
- Hot swap battery case
- Parallelable to 20 kWatts







Field Demonstrations



- Operable on propane and natural gas
- Grid-tie and grid independent operation
- Cogeneration capable, transportable
- Operating for over 4900 hours line NG
- Over 18,000 hrs on latest 5 machines





Acumentrics Confidential



Outline

> Overview Cell Technology Process Developments Generator Developments ➤Coal Systems SECA Phase I Machine Performance > Summary




SECA Product Objectives

- Culminate in a 5-10kW modular stack capable of meeting a number of market requirements.
- > Widen our fuel choices.
- Build upon our knowledge of "ruggedized" products for harsh environments.
- Allow for modular build up to the 100kW class size.
- Allow for integration with military towable power units in the 5-20kW size.




Acumentrics Progress






Performance Comparison






Cell Performance with Doping





Thermal cycling of cells



•101 Thermal Cycles •-0.78%/1000hr overall degradation •Consistent **OCP** through test •3073 hours operation •Cycling continues




Outline

> Overview >Cell Technology Process Developments Generator Developments ➤Coal Systems SECA Phase I Machine Performance > Summary




Fabrication Process Developments





Isopressing Tube for 100kW+ Systems





Plasma Spray Automation



Decreased cost due to automated processing



Outline

> Overview >Cell Technology Process Developments Generator Developments ➤Coal Systems SECA Phase I Machine Performance Summary




Recuperator Development

- Phase II SBIR awarded July 2007 to further investigate Hybrid Solutions
- Full scale metallic and ceramic recuperators tested
- Metallic units are quite effective (82-90%) but oxidation resistance and life are a concern
- Ceramic units have been proven to survive but the effectiveness has been lower (65-75%) than metallic units
- > 80+ Effectiveness required




Hybrid Recuperator Advantages






Hybrid Recuperator





1kW Home CHP Appliance



- First Prototype
- Fully operational:
 - 1kW electric
 - 25kW (85k BTU/hr) Thermal
 - 75-90% total Eff.
 - 33"x22"x18"
 - ~180 lbs total
 - ~100lbs thermal system






Outline

> Overview >Cell Technology Process Developments Generator Developments ≻Coal Systems SECA Phase I Machine Performance > Summary



1 MW SOFC Module


- Four bundles per vessel, 1 MW each
- Pressurized
- 2 meter long tubes
- 13 Interconnects






100MW Coal Fueled SOFC Plant

- Multiple vessels
- Two heat exchangers





Future Gen Fuel Cell





Stack Testing: Recirculated Steam

•Operation condition on July 30 •SECA stack technology utilizing 800C recirculation blower •Operation time: total about 890 hrs •Electric power: DC 8.8kW AC 7.1kW •Electric Efficiency 52% DC LHV 43% AC LHV •Overall efficiency: 84%LHV (70deg-C hot water)



Testing on JP-8



Load following within 30
seconds (manual)
Should be faster when integrated
S/C<=1; low water requirements

5.5hr total testing
Reformer startup (cold to operating) <10min
Fully stable reformer operation in 20min

One day test
Achieved 27%
efficiency
At higher FU, expect to hit ~31%



Outline

> Overview >Cell Technology Process Developments Generator Developments ➤Coal Systems SECA Phase I Machine Performance > Summary



SECA Performance Results

	Goal set by SECA	Acumentrics Phase I Generator	NETL Testing
Peak Power DC	3-10kW	6.1kW	6.2kWDC (NETL)
Degradation Rate %/500hr	≤2%/500hr	-0.00035% /500hr	-1.5%/500hr
Peak Efficiency %	35%-55%	36.9%	>35%
Availability %	>80%	97.5%	96% (including startup, testing, thermal cycles, and grid failures)
Transient Power Degradation %	<1%	0.75%	Not measurable
Cost \$/kW	<\$800/kW	\$729/kW	



NETL Testing Summary

- 890hrs total testing
- 2172 kW-hr produced, 6.2kWDC(net) peak power, ten power cycles, four efficiency points
- 856 hr >1500W net DC
- 3 thermal cycles (one deep)
- 96% availability (including all testing, startup, and grid failures)



SECA generator operation

>4694 hrs operation (as of July 30, 2007)
> 11,402kW-hr produced
> 10 Thermal cycles
> 20 power cycles
> Degradation not measurable
> 6.2kWnetDC peak



Summary

- Moved into Phase II based on successful completion of Phase I goals
- Tripled Power Density over Program Start
- Minimized Degradation (including thermal cycles)
- Significantly Advanced and Simplified Design
- Reduced Cost & Weight and Improved System Density
- Significant progress toward coal-based gas compositions and larger cells and systems



Acknowledgement



Strategic Alliance Partners National Park Service UAF CERL EPRI Propane Energy Research Council



Department of Energy-National Energy Technology Laboratory Heather Quedenfeld, Project Manager