


Imperial Irrigation District

In cooperation with:
Parsons Water & Infrastructure Inc.
Bookman-Edmonston
U.S. Bureau of Reclamation
Dr. Paul Krausman
EcoSystem Restoration Associates
ASM Affiliates



Colorado River Citizens Forum IVC Presentation

All American Canal Project



Colorado River Basin



Canal Lining Project

- Component of Colorado River Quantification Settlement Agreement
- In conjunction with lining of a portion of the Coachella Canal settles a water rights dispute and litigation dating to the 1960s
- Provides 67,700 ac-ft/yr of water
- SDCWA will receive 56,200 ac-ft annually
- SLR will receive 11,500 ac-ft annually


History of the All American Canal Lining Project

- Congressional authorization of the Project was under PL 100-675, Title II signed into law by the President on November 17, 1988
- Concrete lining will begin just downstream of Pilot Knob (~Station 1170+27) to Drop 4, a total of about 29 miles
- During preparation of the EIS/EIR the Project was modified to begin at Station 1250+00 and end at Drop 3 (23 miles) due to:
 - Major environmental issues between Drops 3 & 4 and costs to mitigate such
 - Desire to locate the starting point further away from Pilot Knob, (a sacred area of the Quechan Indians) to eliminate any potential environmental/cultural conflicts
- Approved the Record of Decision (ROD) on July 29, 1994


History of the All American Canal Lining Project

- Completed and filed EIS/EIR in July 1994
- Reclamation undertook a Re-examination and Analysis of 1994 FEIS/EIR and ROD which determined said documents remained current with the proposed action
- California State Legislature passes SB 1765 continuously appropriating \$200 million with \$126 million set aside for this Project. This bill was signed into law by the Governor on September 24, 1998
- California voters in 2003 approve Proposition 50; adds \$9.65 million to Project for total of \$135.65 million
- California State Legislature (Proposition 84) approved an additional \$17.4 million for the project in November of 2006
- Quantification Settlement Agreement (QSA) and its related documents signed on October 10, 2003 with the Project a key component to reduce California's water use to its 4.4 million acre-feet apportionment

AACLP Project Location




AACLP Alignment




All-American Canal Typical Section

Proposed Lined Section
1.75H:1V side slope Reaches 1 & 2
2H:1V side slope Reach 3

Existing Unlined Section 2H:1V side slope



67,700 Acre-Feet per Year of Water Conserved from Lining the All-American Canal



How does completing 78% of the project result in recovering 97% of the seepage water?

The seepage recovery by reach is as follows:

Reach	ac-ft	Cumulative ac-ft
1	50,850	50,850
2	14,700	65,550
3	2,150	67,700

Project Challenges

Project team worked diligently on a fast-track basis to address a number of design, construction, scheduling, and cost issues to minimize costs (construction, environmental, and operations/maintenance) yet optimize the new canal facilities and address the required environmental mitigation.

Design Challenges

- New parallel alignment to minimize canal excavation, rights-of-way, and dewatering
- Reach 1B is most difficult—a number of alternatives were considered. The embankment in-canal alignment was selected
- Project has and will continue to be impacted by increases in fuel, cement, and to a smaller extent steel prices
- Working together to ensure that all state funds required based on current schedule are available

Current Status


- Design is complete but lawsuits are currently preventing construction for beginning
- Lawsuit resulted in a District Court decision in favor of the project. Plaintiff appeal with 9th Circuit resulted in an injunction on August 25th 2006
- Project is currently in the hands of the 9th Circuit with some type of court action occurring tomorrow
- Current schedule indicates construction will begin in June of 2007 and be completed in the Spring of 2010

Current Status


- Have negotiated with Ames/Coffman to maintain their contract in anticipation of a court decision in favor of moving forward with the project
- Currently in negotiations with Kiewit Pacific
- Current schedule indicates construction will begin in June of 2007 and be completed in the Spring of 2010

Canal Photos





AACLP Project Organization



AACLP OM&R Coordinating Committee



IID prepares O&M plan for All-American Canal

Thank You Questions?