

FLORIDA SOLAR ENERGY CENTER

A Research Institute of the University of Central Florida





Industrialized Housing Partnership http://baihp.org

September 1, 1999 - October 31, 2004

Status: April 10, 2001








Goal 1

Cost effectively reduce the energy use of industrialized houses by up to 50% and document through field monitoring.





Goal 2


Provide technical assistance that results in the construction of thousands of energy-efficient industrialized houses every year while enhancing indoor air quality, building durability, and construction productivity.





Make our partners pleased and proud to be working with us.






BAIHP Team

Sponsors

- U.S. DOE Office of Building Technology State and Community Programs
- Florida Energy Office of the Florida Department of Community Affairs
- Northwest Energy Efficiency Alliance
- Prime Contractor

Florida Solar Energy Center (FSEC) of the University of Central Florida (UCF)






BAIHP Team

- Subcontractors
 - Washington State University Energy Program with Oregon Office of Energy and Idaho Dept. of Water Resources
 - > UCF Department of Industrial Engineering
 - > American Lung Association of Central Florida
 - > D.R. Wastchak LLC, Phoenix, AZ
 - Florida H.E.R.O., Gainesville, FL






Home Manufacturer and Builder Team Members

- American Energy Efficient Homes and Investments, Inc.
- Atlantic Design and Construction (Production builder)
- Barker–Coleman Communities (Production builder)
- Beck Builders
- Cavalier Homes (HUD Code manufacturer)
- Centex Homes (Production builder)
- Fallman Design and Construction






Home Manufacturer and Builder Team Members (Cont)

- Fleetwood Homes (HUD Code manufacturer)
- G.W. Robinson (Production builder)
- Habitat for Humanity International (Affordable housing builder)
- Landmark Homes (Production builder)
- Neuffer Homes and Development (Production builder)
- Palm Harbor Homes (HUD Code manufacturer)
- Southern Energy Homes (HUD Code manufacturer)
- Valley Manufactured Housing (HUD Code manufacturer)






Supplier Team Members

- Friedrich Air Conditioning
- Energy Conservatory
- Engineered for Life
- Hard Cast
- LaSalle Air Systems
- Nomaco, Inc.
- Owens Corning Sales, Northwest Region
- Tyvek Weatherization Systems
- York International, Mfg. Housing Division (Coleman Brand Equipment)





Other Collaborators

- American Lung Association of Florida
- ASERTTI
- Building Science Consortium
- Energy Rated Homes of Nevada
- Florida Power Corporation
- Hickory Consortium
- Home Builders Association/Mid-Florida
- North Caroling A&T University
- Pacific Northwest National Laboratory
- Portland Cement Association
- Stevens Associates (Home Ventilation Institute)
- Washington Manufactured Housing Association





FSEC


David Beal, Philip Fairey, Janet McIlvaine, Neil Moyer, Danny Parker, Rob Vieira

WSU Mike Lubliner, Mike McSorley UCFIE

Mike Mullens

PROJECT DIRECTOR: Subrato Chandra, FSEC






BAIHP Highlights

- 8,000+ Energy efficient homes
- Habitat for Humanity
- Moisture problems in HUD Code housing
- Field monitoring
- Unvented attics and "cool" roofs
- Green Housing
- Healthy Housing
- Innovations in manufacturing technology
- Portable classroms
- EnergyGauge USA





8,000+ Energy Efficient Homes Produced with BAIHP Technical Assistance

Homes manufactured to Energy Star or greater savings (HERS score=86)

Homes by D.R. Wastchak, Phoenix, AZ	2,064	(through 3/01)
Homes by FL H.E.R.O, Gainesville, FL	249	(through $2/01)$
Super Good Cents homes west of the cascad	es	
w/low energy ventilation systems	112	(through 7/00)
Palm Harbor Homes	005	(through 2/01)
Habitat for Humanity	018	(through10/00)
Subtotal	2,448	


 Homes produced with a HERS score of around 85 (25% better than MEC, 30%-50% better than Hud Code)

Other SGC/Natural Choice Homes4,694Energy Efficient Homes (PHH div. In NC)1,259

Subtotal 5,953

(through 1/01) (through 8/00)






Transforming Manufactured Housing Duct Construction



led to condensation, mold, and decay.



improves IAQ and energy efficiency.

Team members producing houses with airtight ducts with mastic

> **Palm Harbor Homes Cavalier Homes** Southern Energy Homes <u>7,000</u> homes/yr Total

11,000 homes/yr 10,000 homes/yr 28,000 homes/yr




Super GOOD CENTS/Natural Choice

The Last Decade










Why It's Important

- Manufactured Homes represent <u>45% to 50%</u> of all new electrically heated homes in the Northwest.
- The HUD Thermal Standards <u>do not</u> capture all cost-effective electricity savings.






Super Good Cents/Natural Choice vs. Site Built Energy Codes




What We've Accomplished -Energy Efficient Housing








Northwest Manufactured Housing Shipments and SGC/NC Market Share 1981 - 1998



SGC/NC Makret Share


Northwest Power Planning Council



Homes by Florida H.E.R.O.

<u>Type</u>	Subdivision (builder)		<u>To Date</u>	Next 12mos
SFD	Mentone (Atlantic Design)	454	200	75-100
Town Homes	Monticello (HKW Enterprises)	112	100	12
Town Homes	Williamsburg (HKW Enterprises)	154		35-50
Apartments	Lewis Place (Lewis Place)	112	112	0
SFD	Cedar Grove II (City of Gainesville)	139	44	30+
SFD	Willowcroft (Spain Construction)	34	7	10+
SFD	Granite Park (All American Homes)	39	4	10+






Homes by Florida H.E.R.O. (Cont.)

<u>Type</u>	Subdivision (builder)	<u>Total</u>	<u>To Date</u>	Next 12mos
Mixed	Union Street Station (McGurn)	51	51	0
SFD	Town of Tioga (Dibros)	?	?	10+
SFD	Top of the World (Kenneth Colen)	120	4	75+
SFD	Cobblestone (G.W. Robinson)	275	0	10
SFD	Heathcliff (Beck Builders)	?	1	?
SFD	Brookfield (??)	139	17	15+
	Other small builders			<u>150+</u>
			Total	420 +





CONTINENTAL HOMES	<u>Total</u>	<u>Complete</u>	Next 12 mos
Mesquite Canyon	949	854	95
Meridian Point	537	199	231
Crystal Gardens	285	54	117
Adobe Highlands	403	351	52
Ironwood	230	156	74
Wildcat Ridge	261	248	13
Canyon Trails	611	49	318
Mesafield	62	19	43






Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership





Builder: PHH Plant City

Rater: David Beal

Rater Phone: 407-638-1433

Energy Efficient Features

Roof/Attic/Ceiling: Under Attic R-33, Rad.B

Walls: R-19

Floors: Raised R-11

Duct System: R-6

Windows: DBL, Tint

HVAC: SEER 12, HSPF 7.5

Appliances: one refrigerator

Lights: firct area 221 incndt are

Water Heater: Electric EF .87

Solar System: none





FLORIDA SOLAR ENERGY CENTER* SAVING THE EARTH SAVING YOUR MONEY ID Number: PHH-FLR1PA 2

Project Number: Date Completed: 10/00 HERS Rating: 89.8

Test Results

House CFM50:	Ī
House ACH50:	1
Ducts CFM25 total: 36	Ī
Ducts CFM25 (to out): 0.1	Ī
Pressure Pan Supply Avg: N/A	1
Pressure Pan Return Avg: N/A	

Other Features/Comments

Home Won Plant City Builder's Association's Parade of Home's Home of the Year

Certificate of Validation



and the party of the

The home built by

diamin Anese sussion of the

Palm Harbor Homes/Plant City

at 563 Chance Dr., Lakeland FL has been certified to be compliant with the U.S. Environmental Protection Agency's ENERGY STAR® Homes criteria.

ENERGY STAR Homes use at least 30% less energy for heating, cooling and water

Heating than comparable homes built to the Model Energy Code.

The U.S. EPA hereby recognizes Palm Harbor Homes/Plant City for its contribution in reducing pollution through energy efficiency

Date: October 12, 2000

Home Energy Rating: 89.8 (out of 100) Verification Organization: FSEC/BAIHP

Signed:

Brian Ng ENERGY STAR Homes Customer Services Coordinator www.energystar.gov/homes



Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership



Living Area:	1916
Address:	7220 SW 80 Terrace
	Gainesville, FL 32608
Community	Mentone

Community: Mentone

Builder: Atlantic Design

Rater: Florida H.E.R.O.

Rater Phone: (352) 336-2060

Energy Efficient Features

Roof/Attic/Ceiling: Under Attic R-30

Walls: R-13

Floors: slab on grade

Duct System: R-6

Windows: DBL, Clear

HVAC: SEER 12, AFUE .8

Appliances: one refrigerator

Lights:

Water Heater: Gas EF.59

Solar System: none





FLORIDA SOLAR ENERGY CENTER* ID Number: AD5-25

Project Number:

Date Completed: 10/00 HERS Rating: 86.7

Test Results

House CFM50: 1305	-
House ACH50: 4.1	_
Ducts CFM25 total:N/A	
Ducts CFM25 (to out): N/A	_
Pressure Pan Supply Avg: 0.16	_
Pressure Pan Return Avg: 0.23	

Other Features/Comments

This BAIHP partner was honored as the EPA Energy Star Small Builder of the Year.

Certificate of Validation



Atlantic Design & Construction

at 7220 SW 80 Terr., Gainesville, FL

satisfies the ENERGY STAR[®] Homes criteria of the

U.S. Environmental Protection Agency. ENERGY STAR Homes use at least 30% less energy for heating, cooling and water. heating than comparable homes built to the Model Energy Code.

The U.S. EPA hereby recognizes Atlantic Design & Construction for progress in reducing pollution through energy efficiency.

Signed:

Pan Palk

Sam Rashkin ENERGY STAR Homes Program Manager

Date: October 24, 2000-

Home Energy Rating: 86.7 (out of 100) Verification Organization: Florida HERO / BAIHP 15220 NW-5th Avenue Newberry, FL 32669



Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership



Living Area:	1552 SF
Address:	260 NW 50th Blvd.
	Gainesville, FL 32607

Community: Monticello

Builder: Millpond Dev. Corp.

Rater: Florida H.E.R.O.

Rater Phone: (352) 336-2060

Energy Efficient Features

Roof/Attic/Ceiling: R-30

Walls: R-13, R-3

Floors: slab on grade

Duct System: R-6

Windows: DBL, Clear

HVAC: SEER 12, AFUE 0.78

Appliances: one refrigerator

Lights:

Water Heater: Natural Gas EF 0.56

Solar System: none





FLORIDA SOLAR ENERGY CENTER* ID Number: mtc-87

Project Number:

Date Completed: 07/00

HERS Rating: 89.7

Test Results

House CFM50: 524	
House ACH50: 2.3	
Ducts CFM25 total:32	
Ducts CFM25 (to out): N/A	
Pressure Pan Supply Avg: N/A	
Pressure Pan Return Avg: N/A	

Other Features/Comments

This 113 unit townhouse development include the following features in all of the homes. All duct work and air handlers are located within the conditioned space. All homes are serviced by a combination hydronic heating system. All homes are serviced by





Living Area:	1623 SF
Address:	6728 SW 81st Street
	Gainesville, FL 32608

Community: Mentone

Builder: Atlantic Design

Rater: Florida H.E.R.O.

Rater Phone: (352) 336-2060

Energy Efficient Features

Roof/Attic/Ceiling: R-30

Walls: R-13

Floors: slab on grade

Duct System: R-6

Windows: DBL, Clear

HVAC: SEER 12, AFUE 0.78

Appliances: one refrigerator

Lights:


Water Heater: Natural Gas EF 0.56

Solar System: none

Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership







ID Number: AD2-01

Project Number:

Date Completed: 07/00

HERS Rating: 86.8

Test Results

House CFM50: 1186	
House ACH50: 4.4	
Ducts CFM25 total:N/A	
Ducts CFM25 (to out): N/A	
Pressure Pan Supply Avg: 0.18	
Pressure Pan Return Avg: 0.2	

Other Features/Comments

This developer/builder continues to include provision for the introduction of fresh air through a filtered duct chase from under an eve or porch to the return side of the distribution system. This also helps to maintain a positively pressurized home.





Building America Industrialized Housing Partnership



Living Area:	1058
Address:	201 Southeast 2nd Aven
	Gainesville, FL 32601

Community: Union Street Station

Builder: Charles Perry Constructi

Rater: Florida H.E.R.O.

Rater Phone: (352) 336-2060

Energy Efficient Features

Roof/Attic/Ceiling: none

Walls: R-13

Floors: raised conc. R-19

Duct System: R-6

Windows: DBL, Clear

HVAC: SEER 10, HSPF 7.2

Appliances: one refrigerator

Lights: 132SF fluorescent

Water Heater: Electric EF .9

Solar System: none






FLORIDA SOLAR ENERGY CENTER* ID Number: USS305


Project Number: Date Completed: 10/00 HERS Rating: 86.0

Test Results

House CFM50: 1012
House ACH50: 6.4
Ducts CFM25 total:59
Ducts CFM25 (to out): N/A
Pressure Pan Supply Avg: N/A
Pressure Pan Return Avg: N/A


Other Features/Comments






BEAZER HOMES	<u>Total</u>	<u>Complete</u>	Next 12 mos
Estrella Mountain Ranch	80	24	40
Estrella Vista	106	85	21
Summerfield	297	202	65
Silverton II	162	57	73
Ashton Ranch	336	302	34
Wildflower	299	120	135
Cimmarron II	48	29	19
Terralea	192	38	115
Acacia Landing	349	17	175
Cypress Landing	286	0	143






RISING STAR HOMES	<u>Total</u>	Complete	Next 12 mos
Citrus Heights	63	60	3
PULTE HOME CORP			
Superstition Foothills Horizon	70	67	3
CENTEX HOMES			
Desert Star	178	0	62






HACIENDA BUILDERS	<u>Total</u>	Complete	Next 12 mos
Santa Rita Ranch	103	36	46
Sundance Ranch	211	84	84
Parkwood Ranch East	72	29	29
Roseview	132	59	59
Mountain Vista Ranch	82	53	25
Corte Sierra	213	53	107





TREND HOMES	<u>Total</u>	Complete	Next 12 mos
Paradise Views	207	52	104
Cambridge Estates	564	23	316
Ironwood II	179	18	107
Arlington Estates	395	40	237
Coronado Ranch	114	6	51





Phoenix, AZ Market - Cost Sharing by Southwest Gas

REPUBLIC HOMES	<u>Total</u>	Complete	Next 12 mos
Rancho Paloverde Estates	108	16	49
COUNTRYWALK HOMES			
Wildflower	32	5	21
Sandalwood	60	12	42
ASTANTE LUXURY COMMUNITIES	5		
Bella Tierra	40	4	12
Gilbert Commons	55	5	17

Total number of homes projected for the next 12 months

<u>3,137</u>





Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership




Living Area:	1968 SF
Address:	6646 N.W. Grand Ave.
	Glendale, AZ 85301
Community:	Palm Harbor Village
Builder:	Palm Harbor Homes

Rater: Daran Wastchak

Rater Phone: (480) 350-9274

Energy Efficient Features







FLORIDA SOLAR ENERGY CENTER* ID Number: ph08

Project Number: Date Completed: 06/00 HERS Rating: 88.9

Test Results

House CFM50: 1135
House ACH50:
Ducts CFM25 total:61
Ducts CFM25 (to out): 15
Pressure Pan Supply Avg: N/A
Pressure Pan Return Avg: N/A

Other Features/Comments





Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership



Living Area	2,286
Address	16728 W. McKinley St.
	Goodyear, AZ 85338

Community: Canyon Trails - Talon Te

Builder: Continental

Rater: D.R. Wastchak, L.L.C.

Rater Phone: (480) 350-9274

Energy Efficient Features

Roof/Attic/Ceiling: Under Attic R-30

Walls: R-13

Floors: slab on grade

Duct System: R-4

Windows: DBL U=.64, SHGC=.52

HVAC: SEER 12, AFUE .8

Appliances: N/A

Lights: N/A

Water Heater: Gas or Electric

Solar System: none



FLORIDA SOLAR



ENERGY CENTER*


ID Number: DRW12

Project Number: Date Completed: 12/00 HERS Rating: 88.6

Test Results

House CFM50: 1895 House ACH50: 5 Ducts CFM25 total:96 Ducts CFM25 (to out): N/A Pressure Pan Supply Avg: N/A Pressure Pan Return Avg: N/A

Other Features/Comments



This certifies that the home built by

Continental

at 16728 W. McKinley St., Goodyear, AZ

satisfies the ENERGY STAR[®] for Homes criteria of the

U.S. Environmental Protection Agency. ENERGY STAR labeled homes use at least 30% less energy for heating, cooling, and water heating than comparable homes built to the Model Energy Code.

The U.S. EPA hereby recognizes Continental for its contribution in reducing pollution through energy efficiency.

Signed:

Brian Ng ENERGY STAR for Homes Customer Services Coordinator December 22, 2000

Verification Organization: D.R. Wastchak LLC / BAIHP

www.energystar.gov





Living Area:	1,400
Address:	16738 W. Melvin St.
	Goodyear, AZ 85338
Community:	Canyon Trails - Palomin
Builder:	Continental
Rater:	D.R. Wastchak, L.L.C.

Rater Phone: (480) 350-9274

Energy Efficient Features

Roof/Attic/Ceiling: Under Attic R-30 Walls: R-13 Floors: slab on grade Duct System: R-4 Windows: DBL U=.64, SHGC=.52 HVAC: SEER 12, AFUE .8 Appliances: N/A Lights: N/A Water Heater: Gas or Electric Solar System: none

Roster of Tested and Rated Homes

Building America Industrialized Housing Partnership





FLORIDA SOLAR ENERGY CENTER*

ID Number: DRW16

Project Number: Date Completed: 12/00 HERS Rating: 88.6

Test Results

House CFM50: 1160
House ACH50: 5.2
Ducts CFM25 total:85
Ducts CFM25 (to out): N/A
Pressure Pan Supply Avg: N/A
Pressure Pan Return Avg: N/A

Other Features/Comments



Certificate of Validation



This certifies that the home built by

Continental

at 16738 W. Melvin St., Goodyear, AZ

satisfies the ENERGY STAR[®] for Homes criteria of the

U.S. Environmental Protection Agency. ENERGY STAR labeled homes use at least 30% less energy for heating, cooling, and water heating than comparable homes built to the Model Energy Code.


The U.S. EPA hereby recognizes Continental for its contribution in reducing pollution through energy efficiency.

Signed:

Brian Ng ENERGY STAR for Homes Customer Services Coordinator December 1, 2000

Verification Organization: D.R. Wastchak LLC / BAIHP

www.energystar.gov



Habitat for Humanity

Task Leader – Janet McIlvaine

Training with HFH International


- 1½ Sessions conducted in 3 of Habitats 8 Regions (NW, SE, and NE)
- Top 70 Affiliates Conference
- > HFH 25th Anniversary (Fall 2001)
- Lecture, Field Work, and Hands On Labs











Habitat for Humanity

Design Assistance to Habitat Affiliates

 Florida, Arizona, North Carolina, West Virginia, South Carolina, Washington, Missouri, & 2000 Carter Project in New York and Georgia

Exemplary Projects


- Lakeland Habitat (FL) HERS Score: 89.8
- Homeowner reports 75% reduction in utility bills











Habitat for Humanity

Survey of Affiliates


 Head count of energy efficient Habitat homes nationwide

Energy Star Examples


- Typical Habitat
 Construction
- > 18 Cities
- > Peer Review in Progress

envio	Construction & Environmental Resources
	Only One Survey Per Affiliate Needed—Thank You
Name	Title Daytime Phone ()
Affiliate	StateCounty(ies)
Would you like the	results of this survey e-mailed to you? Yes No E-mail:
For the year 2001,	how many homes does your affiliate hope to have completed by the end of year?
Part A: Energy S	defined in this survey as "a home predicted to save 30% of heating, cooling, and water heatin, ared to a home meeting the 1993 Model Energy Code and having minimum efficiency heating
	cooling, and water heating equipment"
.,	ny Energy Star® homes has your affiliate built?
	u built some homes that you think may qualify as Energy Star® but have not been wed by a certified home Energy Rater?
an E	available at no cost to your affiliate, would you like to have a home rated to see if it Energy Star® Home?ifesNo. If yes, who should be contacted to arran ing? at
	currently building, or do you plan to build, an Energy Star® Homes or equivalent ram homes within the next year?YesNo
	ist any reasons as to why you do not build Energy Star® or equivalent homes:
We define	"Energy-Efficient" in this survey as "home is affordable to the homeowner to operate"
(6) Which b	est describes your affiliate's building practice? (please check all that apply)
	We have built, or currently build, energy-efficient homes in the past We plan to start building energy-efficient homes soon We would like to learn more about building energy-efficient homes
	e building or have built energy-efficient homes, what building components have
you	made more energy-efficient? (please check all that apply on reverse side)





Moisture Problems In HUD Code Homes




Highest priority research item of the HUD code industry

Collaborating with MHRA

Palm Harbor Homes have not had a single problem home in 2000 after incorporating BAIHP guidelines





Moisture Problems In HUD Code Homes

- Leads to energy waste as homeowners lower a/c setpoint to be comfortable (1° lowering of SP = ~10% increase in cooling energy use.
- Causes...
 - Vapor "barrier" on cold side (interior)
 - Thermostat set below outside dewpoint
 - Oversized A/C or constant operation of blower or clogged condensate drain
 - Long-term negative pressures
 - Duct leaks
 - Door closure
 - Exhaust fans
 - Crawlspaces poorly vented or with standing ground water or lacking ground cover



Moisture Problems Investigated In The Field



Taped plenum failure (looking up)



Mold stain: result of neg. pressure



Flex duct sealing failure



"Drowned duct": H2O in insulation

Moisture Problems Investigated In The Field



Overhead ducts cooling floor




Mold stain of vinyl flooring



Belly board sealing failure



Warped vinyl covered flooring



Finding Solutions: 1 Home

Wall damage - High cooling bills - Fireplace problems

- 2100 sqft 4-bedroom 3-bath
- Building airtightness
 - CFM50 = 3245 (1.54 cfm50 per square foot)
- Duct airtightness
 - CFM25_{total}=430 (20.5% floor area)
 - CFM25_{out} =328 (15.6% floor area)
- Pressure differentials: House wrt Outside

(ideally all \triangle P=0.0)

- > all fans off 0.0 pa
- air handler on -5.6 pa (0 to -3 typical)
- master suite door closed -7.0 pa (0 to -4 typical)
- > all interior doors closed -8.0 pa (0 to -5 typical)









Floor Moisture Experiment



Surrounding conditions maintained at 72F, interior conditions at 85F – 85% Decking materials: Radiant barrier plywood, "Novadeck", plywood.








Field Monitoring

- Side-by-side manufactured homes at NCATU, Greensboro, NC
- Fleetwood-Coleman experiments
- Centex Homes
- Portable classrooms in Washington & Idaho
- WSU Energy House
- Hoak residence
- Please visit www.infomonitors.com





1528 SF Side-by-Side Homes w/Simulated Occupancy NC A&T University, Greensboro, NC



Characteristic

Floor/wall/ceiling insulation Windows Ducts HVAC A/C size (tons) Water heater


Standard

R-11/11/20 single/storm taped SEER 10+ strip 3.0 electric


Building America

R-13/22/33 low-E mastic SEER 12 heat pump 2.0 solar






Building America Goal Achieved !








Monitoring Fleetwood Homes & Coleman Evcon




Duct Leakage Effects

- Energy use
- Airflow delivery
- Pressure differentials

2-Speed A/C Performance





Centex Homes


- Two pairs of occupied homes monitored in Dallas, TX over summer 2000 and winter 2000-2001
- Each pair has one conventional and one insulated concrete form (ICF) home












Approximately 20% cooling energy savings from ICF for these 2-story homes.






Cool Roofs

- **•** Funded primarily by Florida Power & Light Co.
- o 7 Habitat homes monitored in southwest Florida (Ft.Myers)
 - Standard dark shingles with standard ventilation (RGS)
 - Light colored shingles with standard ventilation (RWS)
 - Terra cotta direct nailed S-tile roof (RTB)
 - White S-tile roof (RWB)
 - White flat tile roof (RWF)
 - White metal 5-vee roof (RWM)
 - Standard dark shingles with R-19 sprayed insulation on roof decking and unvented attic (RSL)







Cool Roof Results

Case Description	Cooling	Savings	Peak Demand Reduction		
Case Description	kWh	Percent	kW	Percent	
RGS (Control)	0	0%	0	0%	
RWS (White Shingle)	300	4%	0.48	17%	
RSL (Sealed Attic)	620	9%	0.13	5%	
RTB (Terra Cotta Tile)	180	3%	0.36	13%	
RWB (White S-Tile)	1,380	20%	0.92	32%	
RWF (White Flat Tile)	1,200	17%	0.98	34%	
RWM (White Metal)	1,610	23%	0.79	28%	

* Percentages relative to typical values for average sized detached S. FL homes





Florida Green Building Coalition, Inc.

"To provide a Florida green building designation resulting in environmental and economic benefits."

www.floridagreenbuilding.org

Florida Green Home Standard Checklist Schedule A

NEW HOME REQUIREMENTS: Select measures to obtain the minimum number of points listed for each category. The sum of the minimums totals 160 points. Accumulate at least an additional 40 points of your choice to qualify for the program. If any category minimums cannot be achieved, point deficiencies may be made up by adding the deficiency to the total minimum score of 200. (Example: Applicant elects to achieve only 10 points from a category with a minimum of 15. Applicant may still qualify if total points equal or exceed 200 + [15-10] = 205.) Note that category maximums cannot be exceeded at any time.


EXISTING HOME REQUIREMENTS: Same as for NEW HOME except no minimum point requirement in the Materials and Site categories.

PREREQUISITES: If home site borders a natural water body and/or has a swimming pool or spa, at least one measure from the following Waterfront Considerations and/or Swimming Pool/Spa Prerequisite lists must be incorporated.

Prerequisite	1: Swimming Pool / Spa	(Ref.)	Prerequisite	2: Waterfront Considerations	(Ref.)
	Sanitation system that reduces/elin	ninates		Use of native aquatic vegetation in shor	eline area
	chlorine use (salt water, ionization	, etc.)		Low maintenance plants placed between	n lawn
	Retractable pool cover			and shoreline; no turf adjacent to water	r
	Solar pool heating system			Use of terraces, swales, or berms to slow	N
	Efficient pool pumping			storm water movement into water body	y
	Swimming pool/spa free house			Home site does not border natural water	body

Points Points Achieved Possible Criteria	Points Points Achieved Possible Criteria
Code/Ratings	Energy-efficient appliances/amenities
<u>100</u> 100 Meet Florida Energy Code	3 Energy Star [®] refrigerator
5-50 Confirmed Florida HERS Rating (attac	
5 pts for every HERS pt above 80	3 Energy Star [®] clothes washer
For complete explanation of HERS Rating, see Ref	
Homes are given credit for features including	3 Energy-efficient oven/range
Efficient a/c and heat Solar or efficient water heat	3 Energy-efficient oven/range 1 Buyer given info if none installed
Proper orientation Ducts sealed or in cond. spa	2 Efficient well pumping
Efficient windows Insulation quantity and type	
Radiant barrier Envelope sealing	Energy-efficient lighting
	2 Recessed, sealed IC fixtures
Design	1 Indoor lights are compact fluorescent
1 Cross vent and ceiling fans code credi	
1 Min 100ft ² roofed porch min 3 sides o	2 Max installed lighting wattage < 0.5 W/ft ² 2 Light colored interior walls, ceilings, carpet
1 Passive solar space heat system	floors
1 Passive solar day-lighting	1 Single light in bathroom
1 House shaded on east and west by tree	2 Outdoor lights are fluorescent/elec ballast,
1Passive solar day-lighting1House shaded on east and west by tree1Washer and dryer outside of cond space	pv, low voltage, or have motion detector
1 Light colored roof	
1 Light colored exterior walls	Total points for Category 2 (10 min/25 max
1South roof area for future solar use1Earth sheltered design	
1 Pre-plumb for solar hot water	
1 Centrally locate hot water heater	
1 Efficient envelope volume:surface are	0
1 Dwelling unit attached, zero lot-line, r	
house	

Total points for Category 1 (100 min/150 max)



Healthy House

- Participating in development of ALA national technical standards and program
- Upcoming demonstration project in Orlando on healthy remodeling



Highlights from the UCF Constructability Lab


April 10, 2001





Innovations in Modular Manufacturing

Used Simulation Modeling to Make 2 New Modular Manufacturing Plants More Lean & Agile








Innovations in Module Set

Identified Numerous Opportunities for Improving the Module Set Process




Current Research Efforts

- Support Continued Innovation in Modular Home Manufacturing
 - Improve Quality Systems
 - Move Technology to Shop Floor
 - Become More Lean & Agile
- Support Modular Classroom Manufacturers
 - Integrate Energy Saving Innovations into Production Process








Portable Classrooms

<u>Goal</u>

- To research innovative technologies that enhance the energy efficiency, indoor air quality, and the learning environment in portable classrooms.
- Foster the adoption of appropriate technologies through extensive collaborations and partnerships








Portable Classrooms (Cont.)

- New activity in partnership with the northwest states (Washington, Oregon, Idaho)
- PNNL instrumented 1 classroom in Idaho, 2 in Washington. Data available at <u>www.infomonitors.com</u>
- FSEC to monitor portable in Southern California in partnership with SCE
- Extensive collaboration with sister DOE activities, manufacturing, school boards, and the states.






EnergyGauge USA

- Software for accurate predictions of energy use and ratings
- Based on DOE2.1E with FSEC enhancement
- Passed BESTEST
- When compared to monitored field data, average error ~4% in predicting energy cooling use

Available now! See http://energygauge.com





EnergyGauge USA

<u>F</u> ile	⊻iew	<u>C</u> alcu	ulate <u>R</u> epo	rts R <u>e</u> gistrat	ion <u>H</u> elp							
Proj	ject ID:	4	Bld	lg ID: 1		Code-	Rating Entry	Mode			# of IA	's: 0
Current Window, Number 4 of 4 Orient: W Tint: SHGC[window]=windi # of windows like this one: 1 Window Area Data U-Value and Modifiers Overhang Data • Area: 45 ft ² Type: Low-E Double • Storm? Vidth: 2 ft 2 in Frame: Wood/Vinyl U-value: 0.47 Separation: 5 ft 0 in Height: Int shade: Drapes/blinds Calc. U-Value Comment: Comment:												
-0v	erview	of W	indows					- Po:	st			
	BLDG_	NUM	Window ID	Glass Type	Tint	ing	Orientation	Total Area	(ft²)	Units	Height (ft)	ight (i 🔺
	1		2	-ow-E Double	lGC[windo	w]=windo	E	60		1		
	1		3	-ow-E Double	GC[windo	w]=windo	S	150		1		
	1		4	-ow-E Double	GC[windo	w]=windo	W	45		1		
Right-click for page help, or place cursor in any field and press F1 for context-sensitive help.												
F	'loors(1)	Roof	Ceilings(1)	Doors(2)	Windov	vs(4) VVall	s(1) Inf	iltratio	n	Garage	Sunspace
Site Envelope Equipment												

