# Hall C Infrastructure Projects Update

- Outline
  - Targets
    - Input from tgt group
  - Polarimetry
    - Input from Dave G.
  - Some Other Stuff

**Greg Smith** 

**JLab** 

Jan. 2006





### Target Upgrade- Basic Philosophy

- Need smaller SC for SHMS → new SC
- Need bigger smiles for Gep → new SC
  - Surprise → time now a factor
- Need bigger smiles for SANE/BETA too → new SC
- Qweak → new SC (building on existing sample SC)
- Want to improve reliability & servicibility
- Want to improve performance
  - Less current dependence
  - Higher power
  - Less vacuum motion
- Money more of a problem these days

### Target Upgrade- The Plan


- Toss existing Hall C SC & tgts into storage
  - Keep intact as a deep spare option
  - Loops, cells, HXs, fans, heaters, lifter all stay in old SC in storage
- Build completely new SC & targets based on (latest) Hall A design
  - Can capture (steal) their spares this way:
    - Bellows, HXs, lifter, even some cells. Saves \$\$ & time.
    - New: fans, heaters, instrumentation, feedthroughs, etc.
  - Smaller SC Φ SHMS compatible. On-axis vacuum load. Larger smiles for Gep.
  - No rotation. Solid tgts hung below cryostack:
    - 4-5 tgts ~ 25 x 25 mm<sup>2</sup>, plus 3 optics tgts

### Postponed

(until money and time are both available)

- Re-design of cell blocks to eliminate flow restriction causing large Δρ/ρ(I<sub>beam</sub>)
  - Note this will almost certainly require going to 2 loops (with 2 tgts each) or 3 loops (with 1 tgt each)
- Improved fan motors
- HX re-design to decouple fan from HX
  - Get fan out of HX central bore
- Improved impellers (bigger! v<sub>flow</sub> ~ r<sup>2</sup>)
- Common spares
  - For now A spares C and C spares A

New Hall C Scattering Chamber




### New Scattering Chamber

#### Hall A:



### Hall C (proposed):

- Inner diam. ~ 104 cm
- Height ~ 120 cm
- SOS/SHMS smile:
  - $-36 \text{ cm high } (\sim \pm 20^{\circ})$
  - $-3^{\circ} < \theta < 118^{\circ}$
- HMS smile:
  - -8.5 cm high ( $\sim \pm 4.7^{\circ}$ )
  - $-5.5^{\circ} < \theta < 118^{\circ}$




### The Guts of it

Lifter:


Single motor, -Chain drive, -


3 axis,

bellows



### Hall A's current (waterfall) config.





### From behind

Gas I/O at an extreme back angle to keep clear of spectrometer acceptance

beam

### Hall A machined cells & cell blocks



### What you will notice

- Nothing, hopefully....
  - Same control system
  - Same cell options as now, plus waterfall
    - 3 loops each with 15 & 4 cm cells
    - 4-5 solid tgts, plus optics tgts
  - Same basic 3-axis, single motor lifter mech.
  - No solid tgt rotator (whew!)
  - Less vacuum motion & corresponding survey issues
- Should have fewer IOC reboots
  - Because we will move the tgt IOC out of the hall
- No retraining should be necessary!


### Acc. Maintenance Breaks

- Past:
  - Usually we staff the cryotgt over these 4 day breaks
  - Sometimes we warm up in spite of thermal stress
  - For long breaks we always warm up (and will continue to do so)
- Future: Staffing short breaks sucks!
  - Proposal: Replace LH2 with cold He gas
    - Stay below 30K to avoid transition to warm return
    - Maintain trickle flow of coolant
    - Relieves us of our staffing obligation
    - Downsides:
      - Going sub-atmospheric can introduce ice
      - While unstaffed the target could warm up
      - To recondense again takes time & some (daytime) preparation

### Basel/Hall C Møller Upgrade

#### From Dave G:

 Existing Hall C Møller can do 1% measurements (stat) in a few minutes





- Limitations
  - -Maximum current ~ 10  $\mu\text{A}$  . At higher currents the Fe target depolarizes due to target heating
  - -Measurement is destructive
- Goals for and upgraded Møller
  - Measure beam polarization at 100  $\mu$ A or higher
  - Make measurement quasi-continuously

### Kicker Magnet for High Current Møller Polarimetry

- We can overcome target heating effects by using a fast kicker magnet to scan the electron beam across an iron wire or strip target
- Kicker needs to move beam quickly and at low duty cycle to minimize time on iron target and beam heating
- First generation kicker was installed in Fall 2003


From Chen Yan:





### Kicker + Møller Layout

- · Kicker located upstream of Møller target in Hall C arc
- Beam excursion ~ 1-2 mm at target
- The kick angle is small and the beam optics are configured to allow beam to continue cleanly to the dump



### Kicker Progress to date

·1µ foil

#### From Dave G:


• Fall '03: Kicker + wire

•25µ wire too thick
•Inst. Rates too hi
•Established principle
•Got to 20 µA

80 75 ©<sub>70</sub> No kicker, 4 μm foil ▲ Kicker on, 4 μm foil 65 Kicker on, wire target  $(I_e \times f_{kick} = 2000)$ 60 5 10 15 20 25 0 Current (µA)

• Fall '04: Kicker + Foil

Current (µA)



### Future Plans: Optimized Kicker with "Half-Target"


#### From Dave G:


#### Modify kicker:

 The ideal kicker would allow the beam to dwell on the target for a few μs rather than continuously move across the foil

#### Improve target:

 The 1 μm target is crucial, but we need to improve the mounting scheme to avoid wrinkles and deformations






### Kicker R&D


#### Kicker Current Waveform from Pearson Probe

Base width ~ 600 ns, Reputation ~ 5 kHz, Ipeak ~ 100 A



A1 0,8 U

From Chen Yan:



Current flow

Magnetic field

"Two turn" kicker –  $2 \mu s$  total dwell time!

Quasi-flat top kicker interval

### Møller + Kicker Performance

Configuration	Kick width achieved	Precision	Max. Current
Nominal	-	<1%	2 μΑ
Prototype I	20 μs	few %	20 μΑ
Prototype II	10 μs	few %	40 μΑ
G0 Bkwd. (2006)	3.5-4 μs	Required:2% Goal:1%	80 μΑ
Q <sub>Weak</sub>	2 μs	Required:1% Goal:1%	180 μΑ

## Kicker Summary


- Fast kicker magnet and thin Fe foil target will allow very precise (1% syst.) msrmnts of  $P_{beam}$  at full beam current
- R&D progressing well:
  - The 2 test runs we've had so far have been invaluable in getting the system ready for prime time
  - Next round of tests during commissioning for 60 Bkwrd
    - · New 1µ half-moon foil target
    - Improved (1 µs, step function) kicker
    - High current tests with good statistics
- Our goal:
  - 1% polarization measurements at ~80 μA during GO Backward
  - 1% polarization measurements at 180  $\mu A$  during  $Q_{weak}$

### Hall C Compton Polarimeter

#### From Dave:


- Chicane will be designed at Bates
  - MOU in final stages
  - Chicane PR this FY?
- Laser will be a pulsed green laser
  - PR as late as possible → cheaper & better that way
- Yerevan has built a candidate photon detector
  - Working prototype is lead-tungstate
    - Needs to be characterized with a tagged photon beam
- TRIUMF/UManitoba NSERC grant request submitted to build a Si μ-strip e-detection arm
- Will go between legs of Moller
  - 1st chicane magnet for pol. tgt expts will move downstream & needs to be beefed up
- Installation work needs to begin at next changeover
  - − ~ 6 months of work!

### Compton Chicane and Beamline



### **Beamline**

- Cavity BPMs and BCM now available
  - Electronics too now...
  - Aka "G0 long girder"
  - Also with striplines, OTR, etc.
- Ion Chamber electronics being moved to our access tunnel
  - Big grey panel just past key room
- Massive beamline rework in Moller tunnel being planned for upcoming Compton installation



### **Electronics**

#### From Steve:

- F1 TDC experience during HKS was bad
  - TDCs would crash/freeze
    - Radiation? Hall B has not reported problems with them (just fictitious particles...)
    - Firmware? (upgrades coming)
    - Will learn from upcoming Hall A Gep expt.
  - Spectrometers stay on FB
  - F1's for 3<sup>rd</sup> arm stuff only
- DAQ test stand in EEL for small detector tests

### **Electrical Infrastructure**

#### From Bill:

- New 2.0 MVA transformer bringing power into hall
  - Installed (already used by HKS)
- New DC power supply ordered
  - Portable, general purpose
  - Rated for 9500 A, 170 V
- Arc flash calc's. done




### Infrastructure Infrastructure


- New 4T crane above dump entrance
  - To facilitate shielding placement outside nominal crane radius
- A-can/Bayonet can access platform under construction
  - To facilitate stinging of U-tubes
- Raised platform & ramps in SOS area
  - Meant to be used to move HKS dipole to side
    - But the dipole has not moved
  - Facilitates jig & forklift access
  - For now locks SOS to ~120 degrees



### A-can Platform going in now







ramps

### Ramps & Rails

Rail missing- SOS frozen

### **END**