

Section 620.--STONE MASONRY

\$\$620.01

\$\$620.02

620.01. Add the following:

\$\$620.03

Provide Class ___ masonry with a ___ RF finish for stone masonry guardwalls.

\$\$620.04

Provide Class ___ masonry with a ___ RF finish for stone masonry headwalls.

\$\$620.05

620.04. Add the following after the first paragraph:

\$\$620.06

When removing and resetting stone masonry, clean the exposed faces of the stones of all mortar before resetting. Use hand tools to clean mortar from stones.

\$\$620.07

Set each stone on a full mortar base.

\$\$620.08

620.11. Add the following:

\$\$620.09

Measure stone masonry headwalls (new or removed and reset) by the each.

\$\$620.10

Measure remove and reset stone masonry guardwall by the meter.

\$\$620.11

Measure terminal sections by the each.

\$\$620.12

Measure cleaning stone masonry surface by the square meter

\$\$620.13

Measure remove and salvage stone masonry by the lump sum, or cubic meter.

\$\$620.14

Measure excavation under Section 204.

\$\$620.15

Measure aggregate base under Section 301.

\$\$620.16

Measure graded earth berms under Section 204.

\$\$620.17

620.12. Add the following pay item:

Pay Item

Pay Unit

\$\$620.18

62005 Remove and reset stone masonry guardwall Meter

\$\$620.19

62006 Remove and reset stone masonry headwall Each

\$\$620.20

62007 Stone masonry headwall for __-inch pipe culvert Each

\$\$620.21

62008 Clean stone masonry surfaces Square meter

\$\$620.22

	62009 Remove and salvage stone masonry	Lump sum
\$\$620.23	62010 Remove and salvage stone masonry	Cubic meter